



619/259-3140
619/259-3157 FAX

PHASE II ENVIRONMENTAL SITE ASSESSMENT

FOR THE PROPERTY
REFERENCED AS

**WARNER MESA
ORANGE COUNTY, CALIFORNIA**

PREPARED FOR:

Signal Landmark Corporation
6 Executive Circle, Suite 250
Irvine, CA 92614

PIC Job No. ES7765

December 15, 1998

PIC ENVIRONMENTAL SERVICES
742 GENEVIEVE STREET, SUITE G
SOLANA BEACH, CA 92075

TABLE OF CONTENTS

1.0	INTRODUCTION	1
2.0	BACKGROUND	1
2.1	Site Location and Use	1
2.2	Topography, Geology, and Hydrology	1
3.0	PREVIOUS ENVIRONMENTAL INVESTIGATIONS	2
3.1	Earth Tech, Inc., June 1996	2
3.2	PIC Environmental Services - January 1998	3
4.0	SCOPE OF WORK	4
5.0	FIELD OPERATIONS	5
5.1	Soil Sampling Operations	5
5.2	Soil Vapor Sampling Operations	6
6.0	LABORATORY RESULTS	7
6.1	Soil Sample Results	7
6.2	Soil Vapor Sample Results	8
7.0	DISCUSSION	9
8.0	CONCLUSIONS AND RECOMMENDATIONS	10
TABLE 1	SOIL ANALYTICAL RESULTS	12
TABLE 2	SOIL ANALYTICAL RESULTS	15
TABLE 3	SOIL VAPOR ANALYTICAL RESULTS	16
FIGURES		
Figure 1:	Site Location Map	
Figure 2:	Site Plan	
Figure 3:	Soil Analytical Results	
Figure 4:	Soil Vapor Monitoring Well Configuration	
APPENDICES		
Appendix A:	UST Removal Documentation	
Appendix B:	Laboratory Results	



PIC ENVIRONMENTAL SERVICES

742 GENEVIEVE STREET, SUITE G, SOLANA BEACH, CA 92075

619/259-3140

FAX: 619/259-3157

1.0 INTRODUCTION

PIC Environmental Services (PIC) was contracted by Signal Landmark Corporation to perform a Phase II Environmental Site Assessment (ESA) for the Warner Mesa property located at the northeast corner of Pacific Coast Highway and Warner Avenue, Orange County, California (Figure 1). The objectives of this investigation were to evaluate potential environmental concerns identified during a previous Phase I ESA and to evaluate potential environmental impacts due to the abandoned oil wells at the subject property. Potential environmental impacts were evaluated through the collection and analysis of soil samples and soil vapor samples in the vicinity of the areas of potential concern and the previously abandoned oil wells. This report documents the procedures and findings relative to soil and soil vapor sampling and analysis, and was prepared in general accordance with standard environmental contracting and consulting industry practices.

2.0 BACKGROUND

2.1 Site Location and Use

The subject property is located within an unincorporated area of Orange County and is located in the general vicinity of the intersection of Pacific Coast Highway and Warner Avenue in the Huntington Beach area, California (Figure 1). The subject property consists of an approximately 235 acre parcel covered primarily with open grasslands and with limited woodland areas. Several unpaved roads are present throughout the site. The subject property is bounded to the north by Warner Avenue and Los Patos Avenue, to the east by Bolsa Chica Street, to the south by the East Garden Grove Wintersburg Flood Control Channel, and to the west by the Outer Bolsa Bay (Figure 2). The subject property has been used for limited oil production and agriculture historically. In addition, the subject property was previously occupied by the U.S. Army and the Bolsa Chica Gun Club. The subject property is currently unoccupied.

2.2 Topography, Geology, and Hydrology

The elevation of the subject site varies between approximately 10 feet and 55 feet above mean sea level (Figure 1). The subject property is situated on a mesa which is bounded by the Huntington Harbor, Bolsa Bay, and East Garden Grove Wintersburg Flood Control Channel. Grade on the subject property slopes generally towards the west-northwest. Surface drainage at

the subject property varies, based on the location within the property. Surface water generally flows either to the Huntington Harbor or the Bolsa Bay.

The subject property is located within the Orange County Coastal Plain in the Newport-Inglewood Structural Zone. The Coastal Plain covers approximately 775 square miles, and contains a thick sequence of Quaternary and Tertiary sediments deposited on a basement of pre-Tertiary age metamorphic and crystalline rocks. Faulting and structural deformation have occurred in the Newport-Inglewood Structural Zone since the late Miocene; however the greatest activity has occurred since the late Pleistocene. The Newport-Inglewood fault passes from southeast to northwest through the central portion of the property.

The subject site is underlain primarily by Pleistocene age marine terrace deposits (CDMG, 1981). Surficial and near-surficial sediments are relatively young, consisting of recent-age alluvium and coastal deposits, Upper Pleistocene age terrace deposits, and the Lower Pleistocene age San Pedro Formation. Surface soils are generally sands, silts, and clays, typical of tidal marsh/coastal marine depositional environments.

The site lies within the Santa Ana Pressure Subbasin of the Lower Santa Ana River Basin. Beneficial uses of groundwater include municipal, agricultural, industrial service supply, and industrial process supply (CRWQCB, 1994). Information regarding the depth to groundwater and groundwater gradient direction was unavailable; however, groundwater beneath the subject property is most likely located slightly above mean sea level and flows towards the west-southwest.

3.0 PREVIOUS ENVIRONMENTAL INVESTIGATIONS

3.1 Earth Tech, Inc., June 1996

Earth Tech, Inc. (Earthtech) performed a Phase I Environmental Site Assessment for the subject property in June 1996 in order to identify known and/or potential environmental concerns due to past or present on-site and off-site activities (Earthtech, 1996). The Phase I ESA was conducted in general accordance with ASTM Practice E 1527 and included an on-site inspection, a review of historical aerial photographs, a review of environmental databases, and personal interviews. Earthtech identified several potential environmental concerns which are summarized as follows:

- A fuel dispenser/pump and possible underground storage tank (UST) (area A) at the southwest corner of the property;
- A steel above ground storage tank (AST) (area B) at the northeast corner of the property;

- Inactive soil/groundwater treatment equipment (area C) in the northern portion of the property;
- An above ground 3-stage clarifier (area D) in the northern portion of the property;
- An inactive above ground wet gas pipeline (area E) running southeast to northwest through the central portion of the subject property;
- A possible cluster of ASTs (area F) in the western portion of the property;
- An unknown structure, possibly an AST, (area G) in the western portion of the property;
- A possible cluster of ASTs (area H) at the southwestern portion of the property;
- A former military bunker (area I) in the central portion of the property; and
- A possible AST (area J) at the southeastern corner of the property.

Earthtech recommended collecting and analyzing soil samples from the above mentioned areas in order to assess the possible presence of contaminants.

3.2 PIC Environmental Services - January 1998

Several of the potential environmental concerns identified by Earthtech were addressed by PIC in January 21, 1998 correspondence to Mr. Ed Mountford. The underground storage tank (UST) and fuel dispenser, identified by Earthtech as area A, were removed from the subject property on October 2, 1997. Two (2) soil samples recovered from the beneath the removed UST did not contain detectable concentrations of total petroleum hydrocarbons, benzene, toluene, ethylbenzene, xylenes, or methyl tertiary butyl ether (PIC, 1998). The UST was closed with No Further Action required by the Orange County Health Care Agency, Division of Environmental Health in October 1997. Documentation regarding UST removal operations is provided in Appendix A of this report.

The cylindrical steel AST (area B) observed in the northeastern portion of the property was inspected and it was determined that the AST was used to store and/or treat water that was extracted from a production water well located within approximately 20 feet of the tank (PIC, 1998). PIC concluded that the subject tank was not a potential source of contamination by hazardous or regulated substances.

The soil and groundwater treatment equipment (area C) observed by Earthtech in the northern portion of the property was from mitigation operations performed by Groundwater Technologies,

Inc. (GTI) on behalf of CalResources, Inc. Mitigation measures were conducted in response to a wet gas spill during cleaning (pigging) of the wet gas pipeline. The California Regional Water Quality Control Board (CRWQCB) reportedly issued a written closure letter requiring No Further Action with regards to this matter in April 1996.

PIC personnel uncovered and/or re-abandoned 11 on-site oil exploration and production wells at the subject property between April and November, 1997. No evidence of adverse impacts to the subject property by releases of crude oil, petroleum fuel products, or other potentially hazardous materials as a result of previous oil exploration and production was encountered. The wells were uncovered using backhoe excavation equipment. Soil in the immediate vicinity of the wells was not discolored or stained by petroleum hydrocarbons, nor were petroleum hydrocarbon odors detected. Re-abandonment operations were performed under permits issued by the Resources Agency of California, Department of Conservation, Division of Oil and Gas, and Geothermal Resources.

PIC recommended recovering and analyzing soil samples from the additional areas of potential environmental concern (area D through area J) identified by Earthtech.

4.0 SCOPE OF WORK

The following operations were performed under the supervision of a PIC registered geologist:

- Field investigation of potential environmental concerns identified by Earthtech as area D through area J;
- Recovery and laboratory analysis of soil samples from areas D, E, F, G, and H;
- Recovery and laboratory analysis of soil samples from stockpiled soil consisting of oil well drilling mud and cuttings;
- Installation of seven (7) soil vapor monitoring wells in the vicinity of re-abandoned oil wells; and
- Recovery and laboratory analysis of soil vapor samples collected from the newly installed soil vapor monitoring wells.

5.0 FIELD OPERATIONS

5.1 Soil Sampling Operations

PIC personnel conducted an on-site inspection of the subject property and set stakes on July 28, 1998 in order to assess the location and status of potential environmental concerns identified by Earthtech. Field investigations included inspecting these areas for evidence of previous and/or existing structures and identifying appropriate soil sample locations. Field investigations revealed that the possible former AST location identified by Earthtech as area J was, in fact, the remnants of a concrete retaining wall in the southeast corner of the subject property. Additionally, the possible former military bunker (area I) appears to have been misidentified in the Earthtech report. It is PIC's understanding that the military bunker at the subject property was located in the vicinity of former oil well 151. PIC concluded that this location did not warrant soil sampling and laboratory analyses.

PIC recovered soil samples from areas of potential environmental concern on August 5, 1998 using excavation trench techniques. Trenches were excavated in the vicinity of the potential environmental concerns using backhoe excavation equipment. Trenches were excavated to a maximum depth of approximately five (5) feet below ground surface (bgs). Soil samples were collected from locations exhibiting the possible presence of contaminants, when possible. Soil samples were collected from the teeth of the backhoe excavator bucket using a hand trowel. Each soil sample was packed into a glass jar, capped with a Teflon-lined lid, and stored in an ice-chilled cooler. Soil samples were relinquished to a California-certified analytical laboratory following standard chain of custody procedures.

Soil sample locations, depths, and analytical methods are summarized as follows:

- Five (5) soil samples were recovered from the vicinity of an existing above ground 3-stage concrete clarifier in the northern portion of the property (area D). Soil samples were collected from the native soil to the east and west of the clarifier at one (1) foot below ground surface (bgs) and five (5) feet below ground surface (Figure 2). One additional soil sample (CL3) was collected from soil within the clarifier. Soil samples CL1-1', CL2-1', and CL3 were analyzed for total recoverable petroleum hydrocarbons (TRPH) by EPA Method 418.1, for organochlorine pesticides by EPA Method 8080, and for volatile organic compounds by EPA Method 8260.
- Fourteen (14) soil samples were recovered from the vicinity of the former above ground wet gas pipeline (area E). Soil samples were collected from the native soil at one (1) and five (5) feet bgs from sample locations WGL1 through WGL7 (Figure 2). Soil samples were collected in the approximate locations of elbows in the former pipeline. The fourteen (14) soil samples were analyzed for TRPH by EPA Method 418.1. Soil sample

WGL6-1' was additionally analyzed for hydrocarbon chain distribution by DHS Modified EPA Method 8015.

- Ten (10) soil samples were collected from the vicinity of a possible cluster of ASTs in the western portion of the property (area F). Soil samples were recovered at one (1) and five (5) feet bgs from sample locations F1 through F5 (Figure 2). The five (5) soil samples, collected at one (1) foot bgs, were analyzed for TRPH by EPA Method 418.1, and for organochlorine pesticides by EPA Method 8080. In addition, the soil sample recovered at five (5) feet bgs from sample location F3 was analyzed for organochlorine pesticides by EPA Method 8080.
- Ten (10) soil samples were recovered from the vicinity of a possible former AST in the western portion of the property (area G). Soil samples were recovered at one (1) and five (5) feet bgs from sample locations G1 through G5 (Figure 2). The five (5) soil samples recovered at one (1) foot bgs were analyzed for TRPH by EPA Method 418.1, and for organochlorine pesticides by EPA Method 8080.
- Four (4) soil samples were recovered from the vicinity of a possible cluster of former ASTs in the southwestern portion of the property (area H). Soil samples were recovered at one (1) and five (5) feet bgs from sample locations H1 and H2 (Figure 2). The two (2) soil samples recovered at one (1) foot bgs and the sample recovered at five (5) feet bgs from sample location H1 were analyzed for TRPH by EPA Method 418.1 and for organochlorine pesticides by EPA Method 8080. Soil samples H1-1' and H1-5' were additionally analyzed for hydrocarbon chain distribution by EPA Method 8015.
- Two (2) soil samples were recovered from stockpiled drill-cuttings in the vicinity of abandoned oil well 182 (Figure 2). Soil samples SP1-1 and SP1-2 were analyzed for TRPH by EPA Method 418.1, for hydrocarbon chain distribution by EPA Method 8015, and for CCR Title 22 Metals by EPA Method 6010. Soil samples SP1-1 and SP1-2 were additionally analyzed for soluble barium by the Waste Extraction Test (WET, Title 22, CCR, 66261.100 Appendix II).

5.2 Soil Vapor Sampling Operations

PIC installed soil vapor monitoring wells on August 27, 1998 in the vicinity of seven (7) previously abandoned oil exploration and/or production wells located within proposed residential lots in order to evaluate if mitigation measures were warranted. Soil vapor monitoring wells were installed in the vicinity of the former locations of wells T1, 143M, 152, BL9, BL9A, BL18, and BL23 and were designated as T1-V, 143M-V, 152-V, BL9-V, BL9A-V, BL18-V, and BL23-V, respectively (Figure 2).

Soil vapor monitoring wells were installed using direct-push technology. Expendable probe tips with attached 6-inch long stainless steel screen implants were driven to a depth of approximately ten (10) feet bgs in the vicinity of wells T1, 143M, 152, BL18, and BL23. Screen implants were driven to a depth of six (6) feet bgs and eight (8) feet bgs in the vicinity of wells BL9 and BL9A, respectively, due to the occurrence of shallow groundwater in this portion of the property. Mylar tubing extends from the screen implant to the ground surface, and is attached to wooden stakes which are marked with the monitoring well identification number. The annulus around the stainless steel screen implant was backfilled with glass beads, and hydrated bentonite powder was placed from just above the screen implant to the ground surface. The configuration of the soil vapor monitoring wells is illustrated on Figure 3.

Soil vapor samples were collected from the seven (7) newly installed monitoring wells on August 27, 1998. The wells were purged of standing air, and the soil vapor samples were collected in Tedlar bags using a vapor sampling vacuum chamber. Soil vapor samples were relinquished to a California-certified analytical laboratory following standard chain of custody procedures. Soil vapor samples were analyzed for total vapor petroleum hydrocarbons (TVPH) and for benzene, toluene, ethylbenzene, and xylenes (BTEX) by EPA Method TO-3, for methane by ASTM Method D-1946, and for hydrogen sulfide by EPA Method 15/16.

6.0 LABORATORY RESULTS

6.1 Soil Sample Results

The laboratory results of soil samples recovered in the vicinity of areas of potential environmental concern are summarized in Tables 1 and 2, and are briefly summarized as follows:

- TRPH and organochlorine pesticide concentrations were below laboratory detection limits in the three (3) soil samples recovered in the vicinity of the existing concrete clarifier (area D). Tetrachloroethene (PCE) was detected in soil sample CL1-1' at 8.1 µg/kg. No other VOCs were detected.
- TRPH concentrations in the soil samples recovered from beneath the former wet gas pipeline (area E) were below laboratory detection limits (10 mg/kg) in all samples, with the exception of WGL6-1'. TRPH was detected in sample WGL6-1' at 14 mg/kg, however hydrocarbon chain distribution analysis indicated that petroleum hydrocarbon concentrations were below laboratory detection limits (1.0 mg/kg) for all carbon ranges tested (Table 1).
- TRPH concentrations were below laboratory detection limits (10 mg/kg) in the five (5) soil samples recovered from the vicinity of the possible former cluster of ASTs in the

western portion of the property (area F). 4,4'-DDE was detected in soil sample F3-1' at 7.8 µg/kg. No other organochlorine pesticides or VOCs were detected.

- TRPH, organochlorine pesticide, and VOC concentrations were below laboratory detection limits in the five (5) soil samples recovered from the vicinity of a possible former AST in the western portion of the property (area G).
- TRPH concentrations in the vicinity of the possible former cluster of ASTs in the southwestern portion of the property (area H) ranged from below laboratory detection limits (10 mg/kg) to 32 mg/kg. The hydrocarbon chain distribution analysis performed on sample H1-1' indicated that the maximum petroleum hydrocarbon concentration (379 mg/kg) was detected in the C23 to C32 range (Table 1). 4,4'-DDD, 4,4'-DDE, and 4,4'-DDT were detected in sample H1-1' at 13 µg/kg, 39 µg/kg, and 99 µg/kg, respectively. No other organochlorine pesticides were detected. TRPH and organochlorine pesticide concentrations were below the laboratory detection limits in sample H1-5'.
- TRPH concentrations in the stockpiled soil in the vicinity of abandoned well 182 ranged from 133 mg/kg to 301 mg/kg. The hydrocarbon chain distribution analysis performed on sample SP1-1 indicated that the maximum petroleum hydrocarbon concentration (1,080 mg/kg) was detected in the C23 to C32 range (Table 1). The hydrocarbon chain distribution analysis performed on sample SP1-2 indicated that petroleum hydrocarbon concentrations were below laboratory detection limits (1.0 mg/kg) for all carbon ranges tested (Table 1). Total barium concentrations ranged from 1,230 mg/kg to 1,730 mg/kg, and soluble barium concentrations ranged from 7.2 mg/l to 8.8 mg/l. Other metals analysis results are summarized in Table 2.

6.2 Soil Vapor Sample Results

Methane and hydrogen sulfide concentration were below laboratory detection limits (2.0 ppm (v/v) and 0.20 ppm (v/v), respectively) in all soil vapor samples. TVPH concentrations ranged from below laboratory detection limits (1.0 ppm (v/v)) to 2.2 ppm (v/v). The maximum TVPH concentration was detected in soil vapor sample BL9-V-1. Benzene and ethylbenzene concentrations were below laboratory detection limits (0.020 ppm (v/v)) in all soil vapor samples. Toluene concentrations ranged from below laboratory detection limits (0.020 ppm (v/v)) to 0.071 ppm (v/v), and xylenes concentrations ranged from below laboratory detection limits (0.020 ppm (v/v)) to 0.053 ppm (v/v). Soil vapor sample results are summarized in Table 3. Laboratory reports are provided in Appendix B of this report.

7.0 DISCUSSION

The lateral and vertical distribution of soil contaminants appears to be adequately defined in the areas investigated. Contaminant distributions are illustrated in Figure 2 and are summarized as follows:

Petroleum Hydrocarbons

Soil impacted with petroleum hydrocarbons is primarily limited to the stockpiled soil in the north-central portion of the property. The maximum TRPH concentration in this area was 301 mg/kg; however, hydrocarbon chain distribution analysis indicates that the maximum concentration of petroleum hydrocarbons was 1,080 mg/kg in the C23 to C32 range. PIC estimates the volume of petroleum hydrocarbon impacted soil in this area to be less than 200 cubic yards.

Petroleum hydrocarbons were additionally detected in soil samples collected in the vicinity of the former wet gas pipeline (area E) and the possible former cluster of ASTs (area H). The maximum TRPH concentration in these areas was 32 mg/kg, and hydrocarbon chain distribution analysis indicated a maximum hydrocarbon concentration of 379 mg/kg in the C23 to C32 range. Petroleum hydrocarbon impacted soil appears to be limited to between one (1) foot bgs and five (5) feet bgs.

Organochlorine Pesticides

The distribution of organochlorine pesticides appears to be limited to the vicinity of the existing concrete clarifier and the possible former clusters of ASTs (area F and area H). The organochlorine pesticides of primary concern appear to be 4,4'-DDT and its derivatives 4,4'-DDD and 4,4'-DDE. The vertical distribution of pesticides appears to be limited to near surficial soils (less than 5 feet bgs). The maximum concentration of 4,4'-DDD, 4,4'-DDE, and 4,4'-DDT were 0.013 mg/kg, 0.039 mg/kg, 0.099 mg/kg, respectively, which are well below their Total Threshold Limit Concentrations (TTLC) of 1.0 mg/kg. In addition, the maximum contaminant concentrations (0.099 mg/kg) were less than 10 times the Soluble Threshold Limit Concentrations (1.0 mg/l), therefore a Waste Extraction Test (WET) was not warranted.

Volatile Organic Compounds

Tetrachloroethene (PCE) was the only VOC detected. PCE was detected in the soil sample collected at one (1) foot below grade from the native soil east of the existing concrete clarifier (area D) at a concentration of 8.1 µg/kg. There did not appear to be any areas significantly impacted with VOCs, including the above-referenced concrete clarifier.

CCR Title 22 Metals

Several metals were detected in the soil samples recovered from the stockpiled soil in the north-central portion of the subject property, however barium was the only metal detected at a

concentration greater than its soluble threshold limit concentration (STLC). The maximum concentration of total barium was 1,730 mg/kg, which is between the STLC and the total threshold limit concentration (TTL), (100 mg/l and 10,000 mg/kg, respectively); therefore, WET analyses were performed. The WET analyses yielded a maximum soluble barium concentration of 8.8 mg/L, which is less than the STLC for barium (100 mg/L).

Soil Vapor Analyses

Soil vapor sample analyses indicate that the previously abandoned oil wells investigated have not significantly impacted the subsurface soil. Methane, hydrogen sulfide, benzene, and ethylbenzene concentrations were below laboratory detection limits, and the maximum TVPH, toluene, and xylenes concentrations were 2.2 ppm (v/v), 0.071 ppm (v/v), and 0.053 ppm (v/v), respectively. The low concentrations of TVPH, toluene, and xylenes encountered do not reflect a release of liquid or gaseous petroleum hydrocarbons. The additional abandoned oil wells at the subject property were not investigated at this time because they are located within the proposed greenbelt location.

8.0 CONCLUSIONS AND RECOMMENDATIONS

Results of the above-referenced site assessment operations prompt the following conclusions and recommendations:

1. Soil impacted with petroleum hydrocarbons appears to be limited to the stockpiled drill cuttings and mud in the north-central portion of the property. PIC recommends leaving this soil in the proposed greenbelt area.
2. Soil at the subject property does not appear to be significantly impacted with organochlorine pesticides, volatile organic compounds (VOCs), or metals. Based on the concentrations of organochlorine pesticides, VOCs, and metals detected, additional assessment activities and/or mitigation operations do not appear warranted.
3. The subsurface soil at the subject property does not appear to have been significantly impacted by the abandoned oil wells investigated in this assessment. The additional abandoned oil wells, located within the proposed greenbelt, do not warrant investigation at this time due to the proposed land use in these areas.
4. In PIC's judgement, the areas of potential environmental concern, identified by Earthtech and PIC in previous environmental investigations, have been assessed and determined to not pose a significant threat to human health or ecological receptors. Therefore, PIC recommends No Further Action at this time in regards to the potential environmental concerns identified at the subject property.

5. PIC recommends consulting with local and/or state regulatory agencies in order to verify that additional assessment and/or mitigation activities will not be required based on the proposed use of the subject property.

This report is intended for the exclusive use of the above named clients and governmental regulatory agencies only. **PIC Environmental Services** assumes no responsibility nor liability for the reliance herein or hereof by anyone other than the above named clients and governmental agencies. In addition, all laboratory work cited in this report was prepared under the supervision of Cheryl De Los Reyes of Advanced Technology Laboratories in Signal Hill, California, and Maria Jones of Quanterra Environmental Services in City of Industry, California, who are responsible for the contents and conclusions of the laboratory data.

Should you have any questions or comments regarding the contents of this report, please contact me at (619) 259-3140.

Respectfully submitted,
PIC ENVIRONMENTAL SERVICES



Daniel C. Oliver
California Registered Geologist #4781
President



PIC\REPORTS\7765.001

TABLE 1
SOIL ANALYTICAL RESULTS

Sample ID	TRPH mg/kg	HYDROCARBON CHAIN DISTRIBUTION (mg/kg)						4,4'-DDD µg/kg	4,4'-DDE µg/kg	4,4'-DDT µg/kg	VOCs µg/kg
		<C10	C10-C12	C13-C15	C16-C22	C23-C32	>C32				
CL1-1'	<10	<4.0	<4.0	<4.0	PCE - 8.1*
CL2-1'	<10	<4.0	<4.0	<4.0	ND
CL3	<10	<4.0	6.5	<4.0	..
WGL1-1'	<10
WGL1-5'	<10
WGL2-1'	<10
WGL2-5'	<10
WGL3-1'	<10
WGL3-5'	<10
WGL4-1'	<10
WGL4-5'	<10
WGL5-1'	<10
WGL5-5'	<10
WGL6-1'	14	<1.0	<1.0	<1.0	<10	<10	<10
WGL6-5'	<10

TABLE 1
SOIL ANALYTICAL RESULTS

Sample ID	TRPH mg/kg	HYDROCARBON CHAIN DISTRIBUTION (mg/kg)						4,4'-DDD µg/kg	4,4'-DDE µg/kg	4,4'-DDT µg/kg	VOCs µg/kg
		< C10	C10-C12	C13-C15	C16-C22	C23-C32	> C32				
WGL7-1'	< 10	-	-	-	-	-	-	-	-	-	-
WGL7-5'	< 10	-	-	-	-	-	-	-	-	-	-
SP1-1	301	< 1.0	29	52	61	1080	140	-	-	-	-
SP1-2	133	< 1.0	< 1.0	< 1.0	< 10	< 10	< 10	-	-	-	-
F1-1'	< 10	-	-	-	-	-	-	< 4.0	< 4.0	< 4.0	-
F2-1'	< 10	-	-	-	-	-	-	< 4.0	< 4.0	< 4.0	-
F3-1'	< 10	-	-	-	-	-	-	< 4.0	7.8	4.8	-
F3-5'	-	-	-	-	-	-	-	< 4.0	< 4.0	< 4.0	-
F4-1'	< 10	-	-	-	-	-	-	< 4.0	< 4.0	< 4.0	-
F5-1'	< 10	-	-	-	-	-	-	< 4.0	< 4.0	< 4.0	-
G1-1'	< 10	-	-	-	-	-	-	< 4.0	< 4.0	< 4.0	-
G2-1'	< 10	-	-	-	-	-	-	< 4.0	< 4.0	< 4.0	-
G3-1'	< 10	-	-	-	-	-	-	< 4.0	< 4.0	< 4.0	-
G4-1'	< 10	-	-	-	-	-	-	< 4.0	< 4.0	< 4.0	-
G5-1'	< 10	-	-	-	-	-	-	< 4.0	< 4.0	< 4.0	-

TABLE 1
SOIL ANALYTICAL RESULTS

Sample ID	TRPH mg/kg	HYDROCARBON CHAIN DISTRIBUTION (mg/kg)					4,4'-DDD μ g/kg	4,4'-DDE μ g/kg	4,4'-DDT μ g/kg	VOCs μ g/kg
		< C10	C10-C12	C13-C15	C16-C22	C23-C32	> C32			
H1-1'	32	< 1.0	44	102	101	379	85	13	39	99
H1-5'	< 10	< 1.0	< 1.0	< 1.0	< 10	< 10	< 10	< 4.0	< 4.0	< 4.0
H2-1'	< 10	< 4.0	< 4.0	< 4.0

Only compounds detected are summarized in this Table

* - All other volatile organic compound (VOC) concentrations were below laboratory detection limits

PCE - tetrachloroethene

TRPH - total recoverable petroleum hydrocarbons

TRPH analyzed by EPA Method 418.1

Hydrocarbon Chain Distribution analyzed by EPA Method 8015

Pesticides analyzed by EPA Method 8080

Volatile Organic Compounds (VOCs) analyzed by EPA Method 8260

TABLE 2
SOIL ANALYTICAL RESULTS
CCR Title 22 Metals

Sample ID	Antimony mg/kg	Arsenic mg/kg	Barium TTIC mg/kg	Barium STLC mg/kg	Chromium mg/kg	Cobalt mg/kg	Copper mg/kg	Lead mg/kg	Molybdenum mg/kg	Nickel mg/kg	Selenium mg/kg	Silver mg/kg	Thallium mg/kg	Vanadium mg/kg	Zinc mg/kg
SP1-1	0.77	6.1	1730	7.2	14	4.5	16	46	1.8	9.8	0.54	0.30	0.39	19	55
SP1-2	0.89	6.5	1230	8.8	14	6.5	12	17	1.3	10	0.71	0.30	0.76	26	40


Only constituents detected are summarized in this Table
CCR Title 22 Metals analyzed by EPA Method 6010
Barium STLC analyzed by WET (Title 22, CCR, 66261.100 Appendix II)

TABLE 3
SOIL VAPOR ANALYTICAL RESULTS

Sample ID	Methane ppm (v/v)	Hydrogen Sulfide ppm (v/v)	TVPH ppm (v/v)	Benzene ppm (v/v)	Toluene ppm (v/v)	Ethylbenzene ppm (v/v)	Xylenes ppm (v/v)
BL9-V-1	< 2.0	< 0.20	2.2	< 0.020	0.071	< 0.020	0.053
BL9A-V-1	< 2.0	< 0.20	< 1.0	< 0.020	0.020	< 0.020	0.024
BL18-V-1	< 2.0	< 0.20	< 1.0	< 0.020	0.026	< 0.020	0.028
BL23-V-1	< 2.0	< 0.20	1.2	< 0.020	0.034	< 0.020	0.030
T1-V-1	< 2.0	< 0.20	1.8	< 0.020	0.024	< 0.020	0.031
143M-V-1	< 2.0	< 0.20	< 1.0	< 0.020	0.021	< 0.020	0.029
152-V-1	< 2.0	< 0.20	< 1.0	< 0.020	< 0.020	< 0.020	< 0.020

Methane analyzed by ASTM Method D1946
Hydrogen Sulfide analyzed by EPA Method 15/16
TVPH and BTEX analyzed by EPA Method TO-3

FIGURES



SOURCE: U.S.G.S. TOPOGRAPHIC QUADRANGLE
SEAL BEACH, CALIFORNIA
7.5 MINUTE SERIES



SITE LOCATION

SCALE 1:24,000



**PIC ENVIRONMENTAL
SERVICES**
742 GENEVIEVE STREET - SUITE G
SOLANA BEACH, CA 92075

0 1000 2000
SCALE IN FEET

SITE LOCATION MAP

CLIENT:
SIGNAL LANDMARK CORPORATION

FILE:
7765SL (1:1)

PROJECT MANAGER:
DANNY OLIVER


PROJECT NO.:
ES 7665



LOCATION:
**WARNER MESA
ORANGE COUNTY, CALIFORNIA**

DRAFTED BY:
LA JOLLA GRAPHIX

DATE:
DECEMBER 1998


FIGURE:
1






EXPLANATION

- ⊕ 142 ABANDONED OIL WELL
- PROPERTY LINE
- DIRT ROADS
- TOP OF CHANNEL
- - - - - BOTTOM OF CHANNEL
- x - x - x - FORMER WET GAS PIPELINE

 PIC ENVIRONMENTAL SERVICES 742 GENEVIEVE STREET - SUITE G SOLANA BEACH, CA 92075	0 250 500 SCALE IN FEET		SITE-PLAN	
CLIENT: SIGNAL LANDMARK CORPORATION	FILE: 7765SM (1:500)	PROJECT MANAGER: DANNY OLIVER	PROJECT NO.: ES 7765	
LOCATION: WARNER MESA ORANGE COUNTY, CALIFORNIA	DRAFTED BY: LA JOLLA GRAPHIX	DATE: DECEMBER 1998	FIGURE: 2	



NO GRAPHIC SCALE



**PIC ENVIRONMENTAL
SERVICES**
742 GENEVIEVE STREET - SUITE G
SOLANA BEACH, CA 92078

SOIL VAPOR MONITORING WELL CONFIGURATION

CLIENT:

HEARTHSIDE HOMES

PROJECT MANAGER:

DANNY OLIVER

PROJECT NO.:

ES 7765

LOCATION:

WARNER MESA
ORANGE COUNTY, CALIFORNIA

DATE:

DECEMBER 1998

FIGURE:

4

APPENDIX A

UST REMOVAL DOCUMENTATION



COUNTY OF ORANGE
HEALTH CARE AGENCY

EST 11/65
TOM URAM
DIRECTOR

HUGH F. STALLWORTH, M.D.
HEALTH OFFICER

JACK MILLER, REHS
DEPUTY DIRECTOR

MAILING ADDRESS:
2009 EAST EDINGER AVENUE
SANTA ANA, CA 92705-4720

TELEPHONE: (714) 667-3600
FAX: (714) 972-0749

October 24, 1997

PUBLIC HEALTH
DIVISION OF ENVIRONMENTAL HEALTH

Ed Mountford
Signal Bolsa Corporation
4400 MacArthur Boulevard
Newport Beach, CA 92660

Subject: Completion of Tank Removal Project
Former Bolsa Chica Gun Club, Northeast Corner of Warner Avenue and Pacific
Coast Highway, Huntington Beach, CA 92649

Dear Mr. Mountford:

This is in response to your request for a confirmation of the completion of the tank removal project. With the provision that the results for the soil samples obtained during the tank removal on October 2, 1997 were accurate and representative of existing conditions, it is the position of this office that no significant soil contamination has occurred at the above noted facility location.

It should be pointed out that this letter does not relieve you of any responsibilities mandated under the California Health and Safety Code if additional or previously unidentified contamination is discovered at the subject site.

If you have any questions regarding this matter, please contact Peter Peuron at (714) 667-3719.

Very truly yours,

Seth J. Daugherty, REHS
Supervising Hazardous Waste Specialist
Hazardous Materials Management Section
Environmental Health Division

SJD:pp

cc: Danny Oliver, PIC Environmental Services



PIC ENVIRONMENTAL SERVICES

742 GENEVIEVE STREET, SUITE G, SOLANA BEACH, CA 92075

619/259-3140 FAX: 619/259-3157

October 17, 1997

Mr. Peter Peuron
County of Orange
Health Care Agency
Department of Environmental Health
2009 E. Edinger Avenue
Santa Ana, CA 92705

Dear Mr. Peuron:


RE: Underground Storage Tank Removal/Closure
Former Bolsa Chica Gun Club
Bolsa Chica Mesa, Orange County, California

PETROLEUM INDUSTRY CONSULTANTS, INC. (PIC) is pleased to submit the enclosed documents to confirm removal and disposition of a 280-gallon gasoline underground storage tank (UST) on October 2, 1997. These documents include:

- Uniform Hazardous Waste Manifest under which non-RCRA hazardous waste liquid extracted from the removed UST was transported by Nieto and Sons Trucking, Inc. and disposed at the DeMenno Kerdoon treatment facility in Compton, California;
- Tank Disposal Form certifying that the tank was received for destruction at the American Metal Recycling, Inc. facility in Ontario, California; and
- Laboratory analytical results report issued by Transglobal Environmental Geochemistry, Inc. (TEG), a California DOHS-certified laboratory, for analyses of soil samples recovered beneath the removed UST.

The soil samples were analyzed for TPH, BTEX, and MTBE. None of these compounds were detected at the respective laboratory detection limits. On the basis of these results, it is our understanding that the removal and closure of this UST will be formally acknowledged in writing by your agency.

DO NOT WRITE BELOW THIS LINE.



AMERICAN FUEL TANK
METAL
RECYCLING, INC.

2202 South Milliken Avenue
Ontario, CA 91761
(714) 988-8000

No. 42895

TANK DISPOSAL FORM

Date: 10-3-1987
Job #
P. O. #

CONTRACTOR: PIC						
ADDRESS:						
JOB SITE: Signal Blue Corp.						
ADDRESS: 4400 MacArthur Blvd Newport Blvd 92660						
DESTINATION: A.M.R. 2202 S. Milliken Ave., Ontario, CA 91761						
DATE	TIME	PROJECTED TANKS	ORDERED BY:	LIC NO.		
SPECIAL INSTRUCTIONS: Nieto & Son		TIME IN: TIME OUT:				
		QTY	TANKS RECEIVED GALLONS	TYPE F* S*	NET TONS	TOTAL
		280		<input type="checkbox"/> <input type="checkbox"/>	.14	
		500		<input type="checkbox"/> <input type="checkbox"/>	.21	
		550		<input type="checkbox"/> <input type="checkbox"/>	.24	
		1000 - 12 ft		<input type="checkbox"/> <input type="checkbox"/>	.44	
		1000 - 6 ft		<input type="checkbox"/> <input type="checkbox"/>	.61	
		1500		<input type="checkbox"/> <input type="checkbox"/>	.87	
		2000		<input type="checkbox"/> <input type="checkbox"/>	.97	
		2500		<input type="checkbox"/> <input type="checkbox"/>	1.14	
		3000		<input type="checkbox"/> <input type="checkbox"/>	1.32	
		4000		<input type="checkbox"/> <input type="checkbox"/>	1.64	
		5000		<input type="checkbox"/> <input type="checkbox"/>	2.42	
		6000		<input type="checkbox"/> <input type="checkbox"/>	2.84	
		7500		<input type="checkbox"/> <input type="checkbox"/>	3.26	
		8000		<input type="checkbox"/> <input type="checkbox"/>	3.44	
9000		<input type="checkbox"/> <input type="checkbox"/>	3.82			
10000		<input type="checkbox"/> <input type="checkbox"/>	4.33			
12000		<input type="checkbox"/> <input type="checkbox"/>	4.93			
All fees incurred are per load unless specified. Terms are net 30 days from date of invoice. Contractor's signature represents acceptance of terms for payment, and confirms that tank removal complies with State laws.		NO. OF TANKS TOTAL NET TONS				
CONTRACTOR'S SIGNATURE		*F - FIBERGLASS *S - STEEL 105				

CERTIFICATE OF TANK DISPOSAL / DESTRUCTION
THIS IS TO CERTIFY THE RECEIPT AND ACCEPTANCE OF THE TANK(S) AS SPECIFIED ABOVE. ALL MATERIALS SPECIFIED HAVE BEEN COMPLETELY DESTROYED FOR SCRAP PURPOSES ONLY.

AUTHORIZED REP.

GENERATOR COPY

DATE

OCT 16 1987



October 15, 1997

Mr. Danny Oliver
PIC Environmental Services
742 Genevieve Street
Suite G
Solana Beach, CA 92075

SUBJECT: DATA REPORT - BOLSA CHICA GUN CLUB - HUNTINGTON BEACH, CA

TEG Project # 971002-11

Mr. Oliver:

Please find enclosed a data report for the above referenced location. Soil samples were analyzed in TEG's DOHS certified mobile laboratory (CERT #1839).

Project Summary

The following analyses were conducted:

- 2 soils for total petroleum hydrocarbons (TPH) by DOHS Modified EPA Method 8015
- 2 soils for volatile aromatic hydrocarbons (BTEX) by Modified EPA Method 8020
- 2 soils for MTBE by Modified EPA Method 8020

The samples were received chilled in appropriate containers with appropriate labels, seals, and chain-of-custody documentation.

Project Narrative

The results for all analyses and required QA/QC analyses are summarized in the enclosed tables. All calibrations, blanks, surrogates, and spike recoveries fulfill quality control criteria. No data qualifiers (flags) apply to any of the reported data.

TEG appreciates the opportunity to provide analytical services to PIC Environmental Services on this project. If you have any questions relating to this data or report, please do not hesitate to contact us.

Sincerely,

Dr. Blayne Hartman



PIC ENVIRONMENTAL SERVICES PROJECT
BOLSA CHICA GUN CLUB
HUNTINGTON BEACH, CA

TEG Project #971002-11

TPH (DOHS EPA Method 8015 Modified) & BTEX (EPA Method 8020 Modified) ANALYSES OF SOILS

SAMPLE NUMBER	DATE ANALYZED	TPH-GAS		TPH-DIESEL		TPH		TOLUENE (mg/kg)	ETHYLBENZ (mg/kg)	XYLENES (mg/kg)	MTBE (mg/kg)	SURROGATE (%REC)
		C5-C11 (mg/kg)	ND	C12-C24 (mg/kg)	ND	C25+ (mg/kg)	ND					
METHOD BLANK	10/6/97	ND		ND		ND		ND	ND	ND	ND	106%
T1E-6.5'	10/6/97	ND		ND		ND		ND	ND	ND	ND	112%
T1E-6.5' DUP	10/6/97	ND		ND		ND		ND	ND	ND	ND	102%
T1W-6.5'	10/6/97	ND		ND		ND		ND	ND	ND	ND	98%
DETECTION LIMITS		10		10		10		0.050	0.050	0.050	0.050	65%-135%

ND INDICATES NOT DETECTED AT LISTED DETECTION LIMITS

ANALYSES PERFORMED IN TEG'S CA DOHS CERTIFIED MOBILE LABORATORY (CERT #1839)

ANALYSES PERFORMED BY: DR. BLAYNE HARTMAN

DATA REVIEWED BY:

Blayne Hartman

10-16-97



QA/QC REPORT - CALIBRATION DATA

TEG Project #971002-11
DAILY CALIBRATION DATE : 10/6/97

COMPOUND	CALIBRATION RANGE		INITIAL		OPENING		CLOSING / LCS	
	SOIL (ppm)	WATER (ppb)	CALIB DATE	RF	%RSD	AREA	RF	%DIFF
TPH GASOLINE - FID1	20-2000	600-60000	9/7/97	1.085	15.4%	213	0.939	13.5%
						214	1.299	19.7%

TPH DIESEL - FID1	50 - 5000	1500-150000	9/10/97	2.962	3.6%	212	2.358	20.4%
						214	2.336	21.1%

BENZENE	0.1-10	3-300	10/6/97	0.0106	15.2%	101	0.0099	5.7%
TOLUENE	0.1-10	3-300	10/6/97	0.0103	9.7%	103	0.0097	5.8%
ETHYLBENZENE	0.1-10	3-300	10/6/97	0.0124	9.2%	89	0.0113	9.0%
m&p-XYLENES	0.1-10	3-300	10/6/97	0.0100	13.3%	220	0.0091	9.2%
o-XYLENES	0.1-10	3-300	10/6/97	0.0124	10.3%	98	0.0102	17.7%
						94	0.0106	0.7%
						92	0.0109	5.0%
						87	0.0115	7.2%
						194	0.0103	2.9%
						78	0.0127	2.6%

INITIAL RF - AVERAGE RESPONSE FACTOR FROM MULTIPOINT CALIBRATION CURVE

% RSD - LINEARITY OF MULTIPOINT CALIBRATION CURVE (+/- 20% ACCEPTABLE LIMITS)

AREA - AREA COUNTS FROM DAILY CALIBRATION STANDARD

RF - DETECTOR RESPONSE FACTOR FROM MID-POINT CALIBRATION STANDARD

% DIFF - DIFFERENCE, IN PERCENT, BETWEEN THE AVERAGE RF AND THE OPENING OR CLOSING RF

OPENING - MID-POINT CALIBRATION STANDARD ANALYZED BEFORE SAMPLE ANALYSES BEGIN

CLOSING - MID-POINT CALIBRATION STANDARD ANALYZED AFTER SAMPLE ANALYSES ARE COMPLETE

ANALYSES PERFORMED IN TEG'S CA DOHS CERTIFIED MOBILE LABORATORY (CERT #1839)
ANALYSES PERFORMED BY: DR. BLAYNE HARTMAN
DATA REVIEWED BY:

Blayne Hartman
10-16-97



QA/QC REPORT - MS/MSD DATA

MATRIX SPIKE (MS)/MATRIX SPIKE DUPLICATE (MSD) FOR SOILS

ANALYSIS DATE : 10/06/97

TEG Project #971002-11

COMPOUND	SPK CONC (mg/kg)	MS CONC (mg/kg)	%REC MS	MSD CONC (mg/kg)	%REC MSD	RPD	ACCEPTABLE RPD	ACCEPTABLE RECOVERY
TPH GASOLINE	200	223	111.5%	222	111.0%	0.4%	15%	82% - 122%
TPH DIESEL	500	530	106.0%	530	106.0%	0.0%	15%	72% - 112%
MTBE	1.000	1.059	105.9%	1.134	113.4%	6.8%	15%	75%-125%
BENZENE	1.000	1.048	104.8%	1.015	101.5%	3.2%	15%	77% - 109%
TOLUENE	1.000	0.849	84.9%	0.846	84.6%	0.4%	15%	75% - 112%
ETHYLBENZENE	1.000	0.934	93.4%	0.917	91.7%	1.8%	15%	74% - 110%
TOTAL XYLENES	3.000	3.234	107.8%	3.154	105.1%	2.5%	15%	81% - 109%

SPK CONC - CONCENTRATION SPIKED INTO MATRIX

MS CONC - ANALYZED CONCENTRATION OF SPIKED SAMPLE

% REC - PERCENT RECOVERY OF SPIKE FROM MATRIX

RPD - RELATIVE PERCENT DIFFERENCE BETWEEN MATRIX SPIKE AND MATRIX SPIKE DUPLICATE RECOVERIES

ANALYSES PERFORMED IN TEG'S CA DOHS CERTIFIED MOBILE LABORATORY (CERT #1839)

ANALYSES PERFORMED BY: DR. BLAYNE HARTMAN

DATA REVIEWED BY:

Blayne Hartman

10-16-97

CHAIN OF CUSTODY
 Orange County Health Care Agency
 Environmental Health Division
 2009 E. Edinger Ave., Santa Ana, CA 92705
 Telephone: (714) 667-3700

1. ALL SAMPLES ARE TO BE HANDLED AS COURT EVIDENCE, AND ARE TO BE PROPERLY STORED IN A SECURE LOCATION.
2. PLEASE WRITE LEGIBLY.
3. ATTACH THIS FORM TO THE ORIGINAL REPORT OF THE ANALYTICAL RESULTS AND RETURN THEM TO THIS OFFICE. LABORATORY RESULTS RECEIVED WITHOUT PROPER CHAIN OF CUSTODY DOCUMENTATION WILL NOT BE ACCEPTED.

4. TO BE COMPLETED BY LABORATORY ANALYST

LAB NO.: TEG - Project #971002-11

DATE RECEIVED: 10/2/97

SAMPLE(S) CONDITION (PLEASE CHECK):

CHILLED: ✓ COUNTY SEAL(S) INTACT: ✓

CONTAINER IN GOOD CONDITION: ✓

DATE ANALYSIS COMPLETED: _____

ANALYST: _____

5. TO BE COMPLETED BY SAMPLE COLLECTOR

SITE NAME/ADDRESS: BOLSA CHICA
GUN CLUB, HUNTINGTON BEACH

DATE OF COLLECTION: 10-2-97

SAMPLE COLLECTOR/COMPANY: PIC
DANNY OLIVER

TELEPHONE NO.: (619) 259-3140

HCA REPRESENTATIVE: PETER PEURSON

6.

SAMPLE NUMBER	DETERMINATION REQUESTED	SAMPLE DESCRIPTION/COMMENTS	TIME OF COLLECTION
TIE-65	DTSC APPROVED TPIH METHOD FOR GASOLINE	BELOW NORTH END	
	DTSC APPROVED TPIH METHOD FOR DIESEL	OF TANK	
	EPA 8020-BTEX		
	+ MTBE		
TIW-65	SAME 4 ANALYSES	BELOW SOUTHERN END	
	AS ABOVE		


7.

CHAIN OF CUSTODY

1. <u>Peter Peurson</u> SIGNATURE	<u>OCHCA</u> COMPANY/AGENCY	<u>10-2-97 - 9:45</u> INCLUSIVE DATES/TIMES
2. <u>Danny Oliver</u> SIGNATURE	<u>PIC Environmental Services</u> COMPANY/AGENCY	<u>10/2/97 - 9:45</u> INCLUSIVE DATES/TIMES
3. <u>Danny Oliver</u> SIGNATURE	<u>TEG</u> COMPANY/AGENCY	<u>10/2/97 - 2:00</u> INCLUSIVE DATES/TIMES
4. <u>Danny Oliver</u> SIGNATURE	<u>TEG</u> COMPANY/AGENCY	<u>10/2/97 - 2:00</u> INCLUSIVE DATES/TIMES
5. _____ SIGNATURE	_____ COMPANY/AGENCY	_____ INCLUSIVE DATES/TIMES
6. _____ SIGNATURE	_____ COMPANY/AGENCY	_____ INCLUSIVE DATES/TIMES

APPENDIX B

LABORATORY REPORTS



August 14, 1998

ELAP No.: 1838

PIC Environmental Services
742 Genevieve St. Ste G
Solana Beach, CA 92075

ATTN: Mr. Danny Oliver

Client's Project: Warner/Mesa, ES7765
Lab No.: 28093-001/045

Gentlemen:

Enclosed are the results for sample(s) received by Advanced Technology Laboratories and tested for the parameters indicated in the enclosed chain of custody.

Thank you for the opportunity to service the needs of your company. Please feel free to call me at (562) 989 - 4045 if I can be of further assistance to your company.

Sincerely,

A handwritten signature in dark ink, appearing to read 'Cheryl', is written over a light-colored background.

Cheryl De Los Reyes
Technical Operation Manager
CDR/ms

Enclosures

This cover letter is an integral part of this analytical report.

This report pertains only to the samples investigated and does not necessarily apply to other apparently identical or similar materials. This report is submitted for the exclusive use of the client to whom it is addressed. Any reproduction of this report or use of this Laboratory's name for advertising or publicity purpose without authorization is prohibited.

*Mailing Address: P.O. Box 92797 Long Beach, CA 90809-2797
1510 E. 33rd Street Signal Hill, CA 90807 Tel: 562 989-4045 Fax: 562 989-4040*

Client: PIC Environmental Services
Attn: Mr. Danny Oliver

Client's Project: Warner Mesa, ES7765
Date Received: 08/06/98
Date Amended: 08/18/98

Matrix: Soil
Units: µg/kg
Extraction Method: 3550

EPA Method 8080

Lab No.:	Method Blank	28093-001	28093-003	28093-005	28093-022	28093-024							
Client Sample I.D.:	--	CL1-1'	CL2-1'	CL3	F1-1'	F2-1'							
Date Sampled:	--	08/05/98	08/05/98	08/05/98	08/05/98	08/05/98							
QC Batch #:	G988080S268	G988080S268	G988080S26	G988080S26	G988080S26	G988080S26							
Date Extracted:	08/11/98	08/11/98	08/11/98	08/11/98	08/11/98	08/11/98							
Date Analyzed:	08/11/98	08/11/98	08/11/98	08/11/98	08/11/98	08/11/98							
Analyst Initials:	DT	DT	DT	DT	DT	DT							
Dilution Factor:	1	1	1	1	1	1							
ANALYTE	MDL	DLR	Results	DLR	Results	DLR	Results	DLR	Results	DLR	Results	DLR	Results
Alpha-BHC	1.0	1.0	ND	1.0	ND	1.0	ND	1.0	ND	1.0	ND	1.0	ND
Gamma-BHC (Lindane)	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Beta-BHC	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Heptachlor	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Delta-BHC	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Aldrin	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Heptachlor Epoxide	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Endosulfan I	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
4,4'-DDE	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	6.5	4.0	ND	4.0	ND
Dieldrin	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
Endrin	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
4,4'-DDD	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
Endosulfan II	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
4,4'-DDT	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
Endrin Aldehyde	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
Endosulfan Sulfate	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
Methoxychlor	17	17	ND	17	ND	17	ND	17	ND	17	ND	17	ND
Chlordane	17	17	ND	17	ND	17	ND	17	ND	17	ND	17	ND
Toxaphene	170	170	ND	170	ND	170	ND	170	ND	170	ND	170	ND

MDL = Method Detection Limit
ND = Not Detected (Below DLR)

DLR = MDL x Dilution Factor
NA = Not Analyzed

Approved/Reviewed By: _____



Lee Ingvaldson
Department Supervisor

Date: 8/18/98

The cover letter is an integral part of this analytical report.

Client: PIC Environmental Services
Attn: Mr. Danny Oliver

Client's Project: Warner Mesa, ES7765
Date Received: 08/06/98
Date Amended: 08/18/98

Matrix: Soil
Units: µg/kg
Extraction Method: 3550

EPA Method 8080													
Lab No.:	Method Blank	28093-026	28093-028	28093-030	28093-032	28093-034							
Client Sample I.D.:	--	F3-1'	F4-1'	F5-1'	G1-1'	G2-1'							
Date Sampled:	--	08/05/98	08/05/98	08/05/98	08/05/98	08/05/98							
QC Batch #:	G988080S268	G988080S268	G988080S268	G988080S268	G988080S268	G988080S268							
Date Extracted:	08/11/98	08/11/98	08/11/98	08/11/98	08/11/98	08/11/98							
Date Analyzed:	08/11/98	08/11/98	08/11/98	08/11/98	08/11/98	08/11/98							
Analyst Initials:	DT	DT	DT	DT	DT	DT							
Dilution Factor:	1	1	1	1	1	1							
ANALYTE	MDL	DLR	Results	DLR	Results	DLR	Results	DLR	Results	DLR	Results	DLR	Results
Alpha-BHC	1.0	1.0	ND	1.0	ND	1.0	ND	1.0	ND	1.0	ND	1.0	ND
Gamma-BHC (Lindane)	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Beta-BHC	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Heptachlor	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Delta-BHC	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Aldrin	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Heptachlor Epoxide	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Endosulfan I	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
4,4'-DDE	4.0	4.0	ND	4.0	7.8	4.0	ND	4.0	ND	4.0	ND	4.0	ND
Dieldrin	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
Endrin	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
4,4'-DDD	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
Endosulfan II	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
4,4'-DDT	4.0	4.0	ND	4.0	4.8	4.0	ND	4.0	ND	4.0	ND	4.0	ND
Endrin Aldehyde	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
Endosulfan Sulfate	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
Methoxychlor	17	17	ND	17	ND	17	ND	17	ND	17	ND	17	ND
Chlordane	17	17	ND	17	ND	17	ND	17	ND	17	ND	17	ND
Toxaphene	170	170	ND	170	ND	170	ND	170	ND	170	ND	170	ND

MDL = Method Detection Limit
ND = Not Detected (Below DLR)

DLR = MDL x Dilution Factor
NA = Not Analyzed

Approved/Reviewed By: _____

Lee Ingvaldson
Department Supervisor

Date: _____

8/10/98

The cover letter is an integral part of this analytical report.

Client: PIC Environmental Services
Attn: Mr. Danny Oliver

Client's Project: Warner Mesa, ES7765
Date Received: 08/06/98
Date Amended: 08/18/98


Matrix: Soil
Units: µg/kg
Extraction Method: 3550

EPA Method 8080

Lab No.:	Method Blank			28093-036		28093-038		28093-040		28093-042		28093-044	
Client Sample I.D.:	--			G3-1'		G4-1'		G5-1'		H1-1'		H2-1'	
Date Sampled:	--			08/05/98		08/05/98		08/05/98		08/05/98		08/05/98	
QC Batch #:	G988080S268			G988080S268		G988080S268		G988080S268		G988080S268		G988080S268	
Date Extracted:	08/10/98			08/10/98		08/10/98		08/10/98		08/10/98		08/10/98	
Date Analyzed:	08/11/98			08/11/98		08/11/98		08/11/98		08/11/98		08/11/98	
Analyst Initials:	DT			DT		DT		DT		DT		DT	
Dilution Factor:	1			1		1		1		1		1	
ANALYTE	MDL	DLR	Results	DLR	Results	DLR	Results	DLR	Results	DLR	Results	DLR	Results
Alpha-BHC	1.0	1.0	ND	1.0	ND	1.0	ND	1.0	ND	1.0	ND	1.0	ND
Gamma-BHC (Lindane)	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Beta-BHC	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Heptachlor	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Delta-BHC	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Aldrin	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Heptachlor Epoxide	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
Endosulfan I	2.0	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND	2.0	ND
4,4'-DDE	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	39	4.0	ND
Dieldrin	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
Endrin	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
4,4'-DDD	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	13	4.0	ND
Endosulfan II	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
4,4'-DDT	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	99	4.0	ND
Endrin Aldehyde	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
Endosulfan Sulfate	4.0	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND	4.0	ND
Methoxychlor	17	17	ND	17	ND	17	ND	17	ND	17	ND	17	ND
Chlordane	17	17	ND	17	ND	17	ND	17	ND	17	ND	17	ND
Toxaphene	170	170	ND	170	ND	170	ND	170	ND	170	ND	170	ND

MDL = Method Detection Limit
ND = Not Detected (Below DLR)

DLR = MDL x Dilution Factor
NA = Not Analyzed

Approved/Reviewed By: 
Lee Ingvaldson
Department Supervisor

Date: 8/18/98

The cover letter is an integral part of this analytical report.

Spike Recovery and RPD Summary Report - SOIL(ug/kg)

Method : C:\HPCHEM\1\METHODS\PCBPEST1.M (Chemstation Integrator)
 Title : 8081 Pesticides Advanced Technology Laboratory
 Last Update : Fri Jul 31 11:33:52 1998
 Response via : Initial Calibration

Non-Spiked Sample: GB0811A.D

Spike Sample	Spike Duplicate Sample
File ID : GMS0811A.D	GMD0811A.D
Sample : Blank MS	Blank MSD
Acq Time: 11 Aug 1998 12:16 pm	11 Aug 1998 12:51 pm

Compound	Sample Conc	Spike Added	Spike Res	Dup Res	Spike %Rec	Dup %Rec	RPD	QC Limits RPD	QC Limits % Rec
gamma-BHC	0.0	40	43	43	108	109	1	9	50-127
Heptachlor	0.0	40	41	41	101	103	1	15	35-136
Aldrin	0.0	40	44	45	110	112	2	12	47-143
Dieldrin	0.0	80	93	94	116	118	2	8	54-134
Endrin	0.0	80	81	88	102	110	8	16	61-138
4,4'-DDT	0.0	80	67	73	84	91	8	22	15-155

QC Batch #:G988080S268

Reviewed and Approved by: _____

Lee Ingvaldson
Organics Supervisor

Date: 8/14/98

Client: PIC Environmental Services
Attn: Mr. Danny Oliver

Client's Project: Warner Mesa, ES7765
Date Received: 08/06/98
Matrix: Soil
Units: µg/kg

EPA Method 8260

Lab No.:	Method Blank	28093-001	28093-003		
Client Sample I.D.:	--	CL1-1'	CL2-1'		
Date Sampled:	--	08/05/98	08/05/98		
QC Batch #:	P98VOCS148	P98VOCS148	P98VOCS148		
Date Analyzed:	08/07/98	08/07/98	08/07/98		
Analyst Initials:	SMC	SMC	SMC		
Dilution Factor:	1	1	1		
ANALYTE	MDL	DLR	Results	DLR	Results
Benzene	5	5	ND	5	ND
Bromobenzene	5	5	ND	5	ND
Bromodichloromethane	5	5	ND	5	ND
Bromoform	5	5	ND	5	ND
Bromomethane	5	5	ND	5	ND
n-Butylbenzene	5	5	ND	5	ND
sec-Butylbenzene	5	5	ND	5	ND
tert-Butylbenzene	5	5	ND	5	ND
Carbon tetrachloride	5	5	ND	5	ND
Chlorobenzene	5	5	ND	5	ND
Chloroethane	5	5	ND	5	ND
Chloroform	5	5	ND	5	ND
Chloromethane	5	5	ND	5	ND
2-Chlorotoluene	5	5	ND	5	ND
4-Chlorotoluene	5	5	ND	5	ND
Dibromochloromethane	5	5	ND	5	ND
1,2-Dibromo-3-chloropropane	10	10	ND	10	ND
1,2-Dibromoethane	5	5	ND	5	ND
Dibromomethane	5	5	ND	5	ND
1,2-Dichlorobenzene	5	5	ND	5	ND
1,3-Dichlorobenzene	5	5	ND	5	ND
1,4-Dichlorobenzene	5	5	ND	5	ND
Dichlorodifluoromethane	5	5	ND	5	ND
1,1-Dichloroethane	5	5	ND	5	ND
1,2-Dichloroethane	5	5	ND	5	ND
1,1-Dichloroethene	5	5	ND	5	ND
cis-1,2-Dichloroethene	5	5	ND	5	ND

MDL = Method Detection Limit

ND = Not Detected (Below DLR).

DLR = MDL X Dilution Factor

NA = Not Analyzed

The cover letter is an integral part of this analytical report.

Client: PIC Environmental Services
 Attn: Mr. Danny Oliver
 Client's Project: Warner Mesa, ES7765
 Date Received: 08/06/98
 Matrix: Soil
 Units: µg/kg

EPA Method 8260

Lab No.:		Method Blank			28093-001		28093-003			
Client Sample I.D.:		--			CL1-1'		CL2-1'			
ANALYTE	MDL	DLR	Results	DLR	Results	DLR	Results			
trans-1,2-Dichloroethene	5	5	ND	5	ND	5	ND			
1,2-Dichloropropane	5	5	ND	5	ND	5	ND			
1,3-Dichloropropane	5	5	ND	5	ND	5	ND			
2,2-Dichloropropane	5	5	ND	5	ND	5	ND			
1,1-Dichloropropene	5	5	ND	5	ND	5	ND			
Ethylbenzene	5	5	ND	5	ND	5	ND			
Hexachlorobutadiene	5	5	ND	5	ND	5	ND			
Isopropylbenzene	5	5	ND	5	ND	5	ND			
p-Isopropyltoluene	5	5	ND	5	ND	5	ND			
Methylene Chloride	15	15	ND	15	ND	15	ND			
Naphthalene	5	5	ND	5	ND	5	ND			
n-Propylbenzene	5	5	ND	5	ND	5	ND			
Styrene	5	5	ND	5	ND	5	ND			
1,1,1,2-Tetrachloroethane	5	5	ND	5	ND	5	ND			
1,1,2,2-Tetrachloroethane	5	5	ND	5	ND	5	ND			
Tetrachloroethene	5	5	ND	5	8.1	5	ND			
Toluene	5	5	ND	5	ND	5	ND			
1,2,3-Trichlorobenzene	5	5	ND	5	ND	5	ND			
1,2,4-Trichlorobenzene	5	5	ND	5	ND	5	ND			
1,1,1-Trichloroethane	5	5	ND	5	ND	5	ND			
1,1,2-Trichloroethane	5	5	ND	5	ND	5	ND			
Trichloroethene	5	5	ND	5	ND	5	ND			
Trichlorofluoromethane	5	5	ND	5	ND	5	ND			
1,2,3-Trichloropropane	10	10	ND	10	ND	10	ND			
1,2,4-Trimethylbenzene	5	5	ND	5	ND	5	ND			
1,3,5-Trimethylbenzene	5	5	ND	5	ND	5	ND			
Vinyl Chloride	5	5	ND	5	ND	5	ND			
Xylenes (Total)	5	5	ND	5	ND	5	ND			

MDL = Method Detection Limit
 ND = Not Detected (Below DLR).
 DLR = MDL X Dilution Factor
 NA = Not Analyzed

Reviewed/Approved By: _____

Lee Ingvaldson
 Department Supervisor

Date 8/14/98

The cover letter is an integral part of this analytical report.

Spike Recovery and RPD Summary Report - Soil (ug/Kg)

Method : C:\HPCHEM\1\METHODS\PVS0728.M (RTE Integrator)
 Title : VOC 8240/8260B Advanced Technology Laboratory
 Last Update : Tue Jul 28 14:32:43 1998
 Response via : Initial Calibration

Non-Spiked Sample: PB0807D.D

Spike Sample	Spike Duplicate Sample
File ID : PMS0807A.D	PMD0807A.D
Sample : 28084-01 SPIKE	28084-01 SPIKE DUP
Acq Time: 7 Aug 98 7:32 pm	7 Aug 98 8:00 pm

Compound	Sample Conc	Spike Added	Spike Res	Dup Res	Spike %Rec	Dup %Rec	RPD	QC Limits RPD	QC Limits % Rec
1,1-dichloroethene	0.0	100	105	110	105	110	4	20	58-156
benzene	0.0	100	100	108	100	108	7	12	72-134
trichloroethene	0.0	100	101	106	101	106	5	16	55-145
toluene	0.0	100	99	105	99	105	6	16	73-127
chlorobenzene	0.0	100	98	103	98	103	5	11	80-119

QCBATCH#98VOCS148

Reviewed/Approved By: _____

Lee Ingvaldson
 Department Supervisor

Date: _____

8/14/98

Client: PIC Environmental
Attn: Mr. Danny Oliver

Client's Project: Warner Mesa, ES7765

Date Received: 08/06/98

Date Sampled: 08/05/98

Lab No.	Sample I.D.	Analysis	Date Analyzed	Results	Matrix, Units	MDL	DLR	Analyst
28093-001	CL1-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-003	CL2-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-005	CL3	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-006	WGL1-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-007	WGL1-5'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-008	WGL2-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-009	WGL2-5'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-010	WGL3-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-011	WGL3-5'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-012	WGL4-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-013	WGL4-5'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-014	WGL5-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-015	WGL5-5'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-016	WGL6-1'	EPA 418.1 (TRPH)	08/13/98	14	Soil, mg/kg	10	10	MO
28093-017	WGL6-5'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-018	WGL7-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-019	WGL7-5'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-020	SP1-1	EPA 418.1 (TRPH)	08/13/98	301	Soil, mg/kg	10	10	MO

MDL = Method Detection Limit

ND = Not Detected (Below DLR)

DF = Dilution Factor (DLR/MDL)

Reviewed/Approved By: _____

David J. Kern
Department Supervisor

Date: _____

8/14/98

The cover letter is an integral part of this analytical report.

Client: PIC Environmental
Attn: Mr. Danny Oliver

Client's Project: Warner Mesa, ES7765

Date Received: 08/06/98

Date Sampled: 08/05/98

Lab No.	Sample I.D.	Analysis	Date Analyzed	Results	Matrix, Units	MDL	DLR	Analyst
28093-021	SP1-2	EPA 418.1 (TRPH)	08/13/98	133	Soil, mg/kg	10	10	MO
28093-022	F1-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-024	F2-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-026	F3-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-028	F4-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-030	F5-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-032	G1-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-034	G2-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-036	G3-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-038	G4-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-040	G5-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO
28093-042	H1-1'	EPA 418.1 (TRPH)	08/13/98	32	Soil, mg/kg	10	10	MO
28093-044	H2-1'	EPA 418.1 (TRPH)	08/13/98	ND	Soil, mg/kg	10	10	MO

MDL = Method Detection Limit

ND = Not Detected (Below DLR)

DF = Dilution Factor (DLR/MDL)

Reviewed/Approved By: _____

Daniel J. Kern
David J. Kern
Department Supervisor

Date: _____

8/14/98

The cover letter is an integral part of this analytical report.

Skill Recovery and RPD Summary Report

Date: 08/13/98
Sample ID: 28093-013
Matrix: SOIL

QC Batch: TRPH 980813S-1

[illegible]


Date: 8/14/98

Method: 418.1
Analyst: MO
Data File: 8225-2S

Date:	08/13/98
Sample ID:	28093-032
Matrix:	SOIL
QC Batch:	TRPH 980813S-2

[illegible]

Approved by:


David J. Kern
Inorganics Supervisor

Date:

26/4/8

Client: PIC Environmental Services
Attn: Mr. Danny Oliver

Client's Project: Warner Mesa, ES7765
Date Received: 08/06/98
Matrix: Soil
Units: mg/kg
Digestion Method: EPA 3050

EPA 6010 (CCR Metals)

Lab No.:	28093-020	28093-021						
Client Sample I.D.:	SP1-1	SP1-2						
Date Sampled:	08/05/98	08/05/98						
Date Digested:	08/12/98	08/12/98						
Date Analyzed:	08/12/98	08/12/98						
Analyst Initials:	LP/DJK	LP/DJK						
Dilution Factor:	1	1						
ANALYTE	DLR	RESULTS						
Antimony	0.25	0.77	0.89					
Arsenic	0.25	6.1	6.5					
Barium	0.050	1730***	1230***					
Beryllium	0.050	ND	ND					
Cadmium	0.15	ND	ND					
Chromium	0.15	14	14					
Cobalt	0.15	4.5	6.5					
Copper	0.15	16	12					
Lead	0.25	46	17					
Mercury **	0.10	ND	ND					
Molybdenum	0.25	1.8	1.3					
Nickel	0.15	9.8	10					
Selenium	0.25	0.54	0.71					
Silver	0.050	0.30	0.30					
Thallium	0.25	0.39	0.76					
Vanadium	0.15	19	26					
Zinc	0.50	55	40					

MDL = Method Detection Limit

ND = Not Detected (Below DLR).

DLR = MDL X Dilution Factor

* = Only listed constituents designated with TTLC and STLC under CCR Title 22

** = Analysis by EPA Method 7471

*** = Dilution Factor is 100, DLR: 5.0

Reviewed/Approved By: David J. Kerry

David J. Kerry

Department Supervisor

Date: 8/14/98

The cover letter is an integral part of this analytical report.

Method:	EPA7471
Analyst:	DJK
Data File:	80812-2
QA File:	8224-2

Date Analyzed: 08-12-98
Date Digested: 08-12-98
Sample ID: see below
Matrix: SOIL/SOLID

OC Batch NO.: HG980812S-2

[illegible]

Approved by: David J. Kern
David J. Kern
Inorganics Supervisor

Date: 8/14/98

Method: 6010
Analyst: LPJ/L
QA File: 6224-4SS
Data File: ICAP80812-4

Date Analyzed:	08/12/1998
Date Digested:	08/12/1998
Sample ID:	28093-021
Matrix:	Soil
QC Batch No:	ICAP 980812S-1

[illegible]

THE UNIVERSITY OF CHICAGO

Approved by: David J. Kern
David J. Kern
Inorganics Supervisor


Date: 8/6/18

Page 7 of 7

[illegible]

CHAIN OF CUSTODY RECORD

Page 1 of 1



1510 E. 33rd Street
Signal Hill, CA 90807
(562) 989-4045 • FAX (562) 989-4040

FOR LABORATORY USE ONLY:

Batch #: _____ D.O. # _____
P.O. #: _____
Logged By: _____ Date: _____ Time: _____

Method of Transport
Walk-in ☐ Courier ☐ UPS ☐ FED. EXP. ☐ ATL ☒

Sample Condition Upon Receipt
1. COOLER TEMP °C _____ (2-6) 5. SEALED ☒ Y ☐ N ☐
2. CHILLED ☒ Y ☐ N ☐ 6. # OF SPLS MATCH COC ☒ Y ☐ N ☐
3. HEADSPACE (VOA) ☐ Y ☐ N ☐ 7. PRESERVED ☐ Y ☐ N ☐
4. CONTAINER INTACT ☒ Y ☐ N ☐ 8. CONTR. LOT # _____

Client: PIC Environmental Services
Attn: Danny Oliver
Project Name: WATER MESA
Relinquished by: [Signature]
Relinquished by: [Signature]
Relinquished by: [Signature]

Address: 742 E. 33rd St. City: Signal Hill State: CA Zip Code: 90755
Project #: ES-7765 Sampler: Danny Oliver
Date: 8/16/90 Time: _____
Date: _____ Time: _____
Date: _____ Time: _____

TEL: (619) 259-3140 FAX: (619) 259-3157

SHIP TO LAB: _____
TEST: _____
ATL #: _____
DATE: _____
CLIENT I.D.: _____

I hereby authorize ATL to perform the work indicated below:
Project Mgr / Submitter: Michael Oliver Date: 8/16/90
Signature: [Signature]

Special Instructions/Comments: _____

Send Report To: Danny Oliver
Attn: PIC Environmental Services
Co: 742 E. 33rd St.
Address: Signal Hill State: CA Zip: 90755
City: Signal Hill State: CA Zip: 90755

Circle or Add Analysis(es) Requested:
601/8010 (Halogenated Volatiles-GC)
602/8020/807X (Aromatic Volatiles-GC)
603/8030 (Pesticides-GC)
624/8240 (Volatiles-GC)
625/8250 (Volatiles-GC)
601/5M TPH/TEX (COMBINATION)
601/5M TPH/TEX (Diesel-GC)
418.1 (TPH-IR)
Metals - Total (CAC-601/07000)

LAB USE ONLY: Batch #	Lab No.	Sample Description	Sample I.D.	Date	Time	CIRCLE APPROPRIATE MATRIX										PRESERVATION		REMARKS
						DRINKING WATER	AIR	WATER • WASTEWATER	WASTE • LIQUID	WASTE • SOLID	WASTE • SLUDGE	WASTE • SOIL	WASTE • SLUDGE	WASTE • SOLID	WASTE • SLUDGE	TAT #	Type	
28013-020	021	SP1-1		8/16/90	1435													
	022	SP1-2		1435														
	023	F1-1		1450														
	024	F1-5		1450														
	025	F2-1		1457														
	026	F2-5		1500														
	027	F3-1		1505														
	028	F3-5		1510														
	029	F4-1		1515														
	029	F4-5		1520														

• TAT starts 8 a.m. following day if samples received after 5 p.m.

TAT: A= Overnight ≤ 24 hr B= Emergency Next workday C= Critical 2 Workdays D= Urgent 3 Workdays E= Routine 7 Workdays

Container Types: T=Tube V=VOA L=Liter P=Pint J=Jar B=Bedlar G=Glass P=Plastic M=Metal


Preservatives: H=HCl N=HNO₃ S=H₂SO₄ C=4°C Z=Zn(AC)₂ O=NaOH T=Na₂SO₃

Pg. 1 of 2

Pg. 1 of 2

[illegible]

[illegible]



August 25, 1998

ELAP No.: 1838

PIC Environmental Services
1768 Arrow Highway, Suite 102
La Verne, CA 91750

ATTN: Mr. Scott Green

Client's Project: Warner Mesa, ES7765
Lab No.: 28334-001/006

Gentlemen:

Enclosed are the results for sample(s) received by Advanced Technology Laboratories and tested for the parameters indicated in the enclosed chain of custody.

Thank you for the opportunity to service the needs of your company. Please feel free to call me at (562) 989 - 4045 if I can be of further assistance to your company.

Sincerely,

Cheryl De Los Reyes
Technical Operations Manager
CDR/ms

Enclosures

This cover letter is an integral part of this analytical report.

This report pertains only to the samples investigated and does not necessarily apply to other apparently identical or similar materials. This report is submitted for the exclusive use of the client to whom it is addressed. Any reproduction of this report or use of this Laboratory's name for advertising or publicity purpose without authorization is prohibited.

Mailing Address: P.O. Box 9108 Newport Beach, CA 92658
1510 E. 33rd Street Signal Hill, CA 90807 Tel: 562 989-4045 Fax: 562 989-4040

SEP 08 1998

Client: PIC Environmental Services
Attn: Mr. Scott Green

QC Batch #: L988015DS373/1988G20S308
Lab No.: Method Blank
Date Sampled: 08/05/98
Date Received: 08/06/98
Date Extracted: 08/19/98
Date Analyzed: 08/20,21/98
Dilution Factor: 1

Client's Project: Warner Mesa, ES7765

Matrix: Soil

Sample ID.: —
Analyst Initials: SMC

Hydrocarbon Chain Distribution

Hydrocarbon I.D.	% Weight	Results, mg/kg	Detection Limit, mg/kg
<C10	ND	ND	1.0
C10 - C12	ND	ND	1.0
C13 - C15	ND	ND	1.0
C16 - C22	ND	ND	10
C23 - C32	ND	ND	10
>C32	ND	ND	10

ND = Not Detected.

Reviewed/Approved By: _____


Lee Ingvaldson
Department Supervisor

Date: 8/25/98

The cover letter is an integral part of this analytical report.

Client: PIC Environmental Services
Attn: Mr. Scott Green

QC Batch #: L988015DS373/1988G20S308
Lab No.: 28334-001
Date Sampled: 08/05/98
Date Received: 08/06/98
Date Extracted: 08/19/98
Date Analyzed: 08/20,21/98
Dilution Factor: 1

Client's Project: Warner Mesa, ES7765

Matrix: Soil

Sample ID.: WGL6-1

Analyst Initials: SMC

Hydrocarbon Chain Distribution			
Hydrocarbon I.D.	% Weight	Results, mg/kg	Detection Limit, mg/kg
<C10	ND	ND	1.0
C10 - C12	ND	ND	1.0
C13 - C15	ND	ND	1.0
C16 - C22	ND	ND	10
C23 - C32	ND	ND	10
>C32	ND	ND	10

ND = Not Detected.

Reviewed/Approved By: _____

Lee Ingvaldson
Department Supervisor

Date: 8/26/98

The cover letter is an integral part of this analytical report.

Client: PIC Environmental Services
Attn: Mr. Scott Green

QC Batch #: L988015DS373/988G20S308
Lab No.: 28334-002
Date Sampled: 08/05/98
Date Received: 08/06/98
Date Extracted: 08/19/98
Date Analyzed: 08/20,21/98
Dilution Factor: 1

Client's Project: Warner Mesa, ES7765

Matrix: Soil

Sample ID.: SP1-1

Analyst Initials: SMC

Hydrocarbon Chain Distribution			
Hydrocarbon I.D.	% Weight	Results, mg/kg	Detection Limit, mg/kg
<C10	ND	ND	1.0
C10 - C12	2.0	29	1.0
C13 - C15	3.8	52	1.0
C16 - C22	4.5	61	10
C23 - C32	79.2	1080	10
>C32	10.5	140	10

ND = Not Detected.

Reviewed/Approved By: _____


Lee Ingvaldson
Department Supervisor

Date: 8/25/98

The cover letter is an integral part of this analytical report.

Client: PIC Environmental Services
Attn: Mr. Scott Green

QC Batch #: L988015DS373/1988G20S308
Lab No.: 28334-003
Date Sampled: 08/05/98
Date Received: 08/06/98
Date Extracted: 08/19/98
Date Analyzed: 08/20,21/98
Dilution Factor: 1

Client's Project: Warner Mesa, ES7765

Matrix: Soil

Sample ID.: SP1-2

Analyst Initials: SMC

Hydrocarbon Chain Distribution			
Hydrocarbon I.D.	% Weight	Results, mg/kg	Detection Limit, mg/kg
<C10	ND	ND	1.0
C10 - C12	ND	ND	1.0
C13 - C15	ND	ND	1.0
C16 - C22	ND	ND	10
C23 - C32	ND	ND	10
>C32	ND	ND	10

ND = Not Detected.

Reviewed/Approved By: _____

Lee Ingvaldson
Department Supervisor

Date: 8/25/98

The cover letter is an integral part of this analytical report.

Client: PIC Environmental Services
Attn: Mr. Scott Green

QC Batch #: L988015DS373/1988G20S308
Lab No.: 28334-005
Date Sampled: 08/05/98
Date Received: 08/06/98
Date Extracted: 08/19/98
Date Analyzed: 08/20,21/98
Dilution Factor: 1

Client's Project: Warner Mesa, ES7765

Matrix: Soil

Sample ID.: H1-1

Analyst Initials: SMC

Hydrocarbon Chain Distribution			
Hydrocarbon I.D.	% Weight	Results, mg/kg	Detection Limit, mg/kg
<C10	ND	ND	1.0
C10 - C12	6.2	44	1.0
C13 - C15	14.4	102	1.0
C16 - C22	14.2	101	10
C23 - C32	53.2	379	10
>C32	12	85	10

ND = Not Detected.

Reviewed/Approved By: _____


Lee Ingvaldson
Department Supervisor

Date: 8/25/98

The cover letter is an integral part of this analytical report.

Spike Recovery and RPD Summary Report - SOIL

Method : C:\HPCHEM\1\METHODS\CARBON.M (RTE Integrator)
Title : 8015GAS/ 8020 (BTXE)
Last Update : Mon Aug 10 15:03:17 1998
Response via : Initial Calibration


Non-Spiked Sample: 28334-01.D

Spike Sample	Spike Duplicate Sample
File ID : IMS0821A.D	IMD0821A.D
Sample : 28334-01 3ppm MS Gas (+BTEX)	28334-01 3ppm MSD Gas (+BTEX)
Acq Time: 21 Aug 1998 10:30 pm	21 Aug 1998 10:55 pm

Compound	Sample Conc	Spike Added	Spike Res	Dup Res	Spike %Rec	Dup %Rec	RPD	QC Limits RPD	% Rec
Gasoline (mg/kg)	ND	3	2	2	53	56	6	21	41-151
Benzene #2 (ug/kg)	ND	31	20	22	65	70	7	15	42-132
Toluene #2 (ug/kg)	ND	183	110	120	60	66	9	15	42-132

QC BATCH #:I988G20S308

Reviewed and Approved by:


Lee Ingvaldson
Organics Supervisor

Date:

8/25/98

Client: PIC Environmental Services
Attn: Mr. Scott Green

Client's Project: Warner Mesa, ES7765
Date Received: 08/06/98
Extraction Method: 3550
Matrix: Soil
Units: ug/kg

EPA Method 6080 (Pesticides)

Lab No.:	Method Blank	28334-004	28334-006																
Client Sample I.D.:	--	F3-5	H1-5																
Date Sampled:	--	08/05/98	08/05/98																
QC Batch #:	H988080S281	H988080S281	H988080S281																
Date Extracted:	08/19/98	08/19/98	08/19/98																
Date Analyzed:	08/21/98	08/21/98	08/21/98																
Analyst Initials:	DT	DT	DT																
Dilution Factor:	1	1	1																
ANALYTE	MDL	DLR	Results	DLR	Results	DLR	Results												
Alpha-BHC	2	2	ND	2	ND	2	ND												
Gamma-BHC (Lindane)	2	2	ND	2	ND	2	ND												
Beta-BHC	2	2	ND	2	ND	2	ND												
Heptachlor	2	2	ND	2	ND	2	ND												
Delta-BHC	2	2	ND	2	ND	2	ND												
Aldrin	2	2	ND	2	ND	2	ND												
Heptachlor Epoxide	2	2	ND	2	ND	2	ND												
Endosulfan I	2	2	ND	2	ND	2	ND												
4,4'-DDE	4	4	ND	4	ND	4	ND												
Dieldrin	4	4	ND	4	ND	4	ND												
Endrin	4	4	ND	4	ND	4	ND												
4,4'-DDD	4	4	ND	4	ND	4	ND												
Endosulfan II	4	4	ND	4	ND	4	ND												
4,4'-DDT	4	4	ND	4	ND	4	ND												
Endrin Aldehyde	4	4	ND	4	ND	4	ND												
Endosulfan Sulfate	4	4	ND	4	ND	4	ND												
Methoxychlor	17	17	ND	17	ND	17	ND												
Chlordane	17	17	ND	17	ND	17	ND												
Toxaphene	170	170	ND	170	ND	170	ND												

MDL = Method Detection Limit
ND = Not Detected (Below DLR)
DLR = MDL X Dilution Factor
NA = Not Analyzed

Reviewed/Approved By: _____

Lee Ingvaldson
Department Supervisor

Date: _____

8/25/98

The cover letter is an integral part of this analytical report.

Spike Recovery and RPD Summary Report - SOIL(ug/Kg)

Method : C:\HPCHEM\1\METHODS\PCBPEST.M (Chemstation Integrator)
 Title : 8080 Pesticides
 Last Update : Sun Aug 23 15:45:29 1998
 Response via : Initial Calibration

Non-Spiked Sample: HB0821B.D

Spike Sample	Spike Duplicate Sample
File ID : HMS0821B.D	HL0821A.D
Sample :	
Acq Time: 22 Aug 1998 1:40 am	22 Aug 1998 1:11 am

Compound	Sample Conc	Spike Added	Spike Res	Dup Res	Spike %Rec	Dup %Rec	RPD	QC RPD	Limits % Rec
gamma-BHC	0.0	40	28	28	69	69	0	9	50-127
Heptachlor	0.0	40	29	29	73	73	0	12	35-136
Aldrin	0.0	40	35	35	86	86	0	15	47-143
Dieldrin	0.0	80	62	62	75	74	1	8	54-134
Endrin	0.0	80	65	62	81	78	4	16	61-138
4,4'-DDT	0.0	80	59	59	74	74	0	22	15-155

JCBATCH#H988080S281

Reviewed/Approved By: Lee Ingvaldson Date: 8/25/98
 Organics Supervisor

Client: PIC Environmental Services
Attn: Mr. Tim Hersch

Client's Project: Warner Mesa, ES7765

Date Received: 08/06/98

Date Sampled: 08/05/98

*Date Extracted: 08/19/98

*Extraction Method: WET (Title 22, CCR, 66261.100 Appendix II)

[illegible]

MDL = Method Detection Limit

ND = Not Detected (Below DLR)

DF = Dilution Factor (DLR/MDL)

Reviewed/Approved By:

David J. Kern

Department Supervisor

Date:

8/25/98

Date:

Cheryl De Los Reyes

Technical Operations Manager

The cover letter is an integral part of this analytical report.

Method: EPA 6010
Analyst: DJK/JL
Data File: ICP 80821-1
QA File: 8233-3ST


Date Analyzed:	08/21/98
Date Extracted:	08/19/98
Sample ID:	28334-003
Matrix:	STLC Extract

QC Batch No. ICAP: 980821ST-1

[illegible]

Approved by: David J. Kern
Inorganics Supervisor

Date: 8/25/98



September 14, 1998

ELAP No.: 1838

PIC Environmental Services
742 Genevieve St. Ste G
Solana Beach, CA 92075

ATTN: Mr. Danny Oliver

Client's Project: Warner Mesa
Lab No.: 28622-001/007

Gentlemen:

Enclosed are the results for sample(s) received by Advanced Technology Laboratories and tested for the parameters indicated in the enclosed chain of custody.

The samples for Methane, Gas/BTEX, and Hydrogen Sulfide analysis were subcontracted to Quanterra Labs.

Thank you for the opportunity to service the needs of your company. Please feel free to call me at (562) 989 - 4045 if I can be of further assistance to your company.

Sincerely,

A handwritten signature in dark ink, appearing to read 'Cheryl'.

Cheryl De Los Reyes
Technical Operation Manager
CDR/ms

Enclosures

This cover letter is an integral part of this analytical report.

This report pertains only to the samples investigated and does not necessarily apply to other apparently identical or similar materials. This report is submitted for the exclusive use of the client to whom it is addressed. Any reproduction of this report or use of this Laboratory's name for advertising or publicity purpose without authorization is prohibited.

*Mailing Address: P.O. Box 92797 Long Beach, CA 90809-2797
1510 E. 33rd Street Signal Hill, CA 90807 Tel: 562 989-4045 Fax: 562 989-4040*



Environmental
Services

Quanterra Incorporated
18501 East Gale Avenue #130
City of Industry, California 91748

818 965-1006 Telephone
818 965-1003 Fax

September 8, 1998

ADVANCED TECHNOLOGY LABORATORIES
1500 E. 33rd Street
Signal Hill, CA 90807
ATTN: Mr. Val Mallari

ANALYSIS NO.: 133786-0001/0007-SA
ANALYSES: EPA TO3 - BTEX & TVPH
as Gasoline, EPA 15/16 - Hydrogen
sulfide, ASTM-D1946 - Methane
DATE SAMPLED: 08/27/98
DATE SAMPLES REC'D: 08/28/98

PROJECT: 28622


Enclosed with this letter is the report on the chemical and physical analyses for the samples from ANALYSIS NO.: 133786-0001/0007-SA as shown above.

The samples were received by Quanterra Incorporated, City of Industry, intact and with the chain-of-custody record attached.

Please note that ND means not detected at the reporting limits expressed.

The preliminary results were faxed to Ms. Rachelle Arada of Advanced Technology Laboratories on September 4, 1998.

All applicable internal quality control analyses including calibrations, method blanks, duplicate control samples (DCS), and other QC met acceptance criteria. Any matrix-related anomalies are indicated using footnotes within the report. Any other anomalies are reported within the narrative. There are no anomalies associated with this report.



Maria O. Jones
Project Manager

9/8/98

Date
Approved

SAMPLE DESCRIPTION INFORMATION
for
Advanced Technology Laboratories

Lab ID	Client ID	Matrix	Sampled		Received
			Date	Time	Date
133786-0001-SA	28622-001/BL9-V-1	AIR	27	AUG 98	28 AUG 98
133786-0002-SA	28622-002/BL9A-V-1	AIR	27	AUG 98	28 AUG 98
133786-0003-SA	28622-003/BL18-V-1	AIR	27	AUG 98	28 AUG 98
133786-0004-SA	28622-004/BL23-V-1	AIR	27	AUG 98	28 AUG 98
133786-0005-SA	28622-005/T1-V-1	AIR	27	AUG 98	28 AUG 98
133786-0006-SA	28622-006/143M-V-1	AIR	27	AUG 98	28 AUG 98
133786-0007-SA	28622-007/152-V-1	AIR	27	AUG 98	28 AUG 98

EPA TO-3 - BTEX

Client Name: Advanced Technology Laboratories
Client ID: 28622-001/BL9-V-1
LAB ID: 133786-0001-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-5

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Benzene	ND		0.020	ppmv
Toluene	0.071		0.020	ppmv
Ethylbenzene	ND		0.020	ppmv
Xylenes (total)	0.053		0.020	ppmv

ND = Not Detected

EPA TO-3 - BTEX

Client Name: Advanced Technology Laboratories
Client ID: 28622-002/BL9A-V-1
LAB ID: 133786-0002-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-5

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Benzene	ND		0.020	ppmv
Toluene	0.020		0.020	ppmv
Ethylbenzene	ND		0.020	ppmv
Xylenes (total)	0.024		0.020	ppmv

ND = Not Detected

EPA TO-3 - BTEX

Client Name: Advanced Technology Laboratories
Client ID: 28622-003/BL18-V-1
LAB ID: 133786-0003-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-5

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Benzene	ND		0.020	ppmv
Toluene	0.026		0.020	ppmv
Ethylbenzene	ND		0.020	ppmv
Xylenes (total)	0.028		0.020	ppmv

ND = Not Detected

EPA TO-3 - BTEX

Client Name: Advanced Technology Laboratories
Client ID: 28622-004/BL23-V-1
LAB ID: 133786-0004-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-5

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 29 AUG 98

Parameter	Result	Qualifier	RL	Units
Benzene	ND		0.020	ppmv
Toluene	0.034		0.020	ppmv
Ethylbenzene	ND		0.020	ppmv
Xylenes (total)	0.030		0.020	ppmv

ND = Not Detected

EPA TO-3 - BTEX

Client Name: Advanced Technology Laboratories
Client ID: 28622-005/T1-V-1
LAB ID: 133786-0005-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-5

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 29 AUG 98

Parameter	Result	Qualifier	RL	Units
Benzene	ND		0.020	ppmv
Toluene	0.024		0.020	ppmv
Ethylbenzene	ND		0.020	ppmv
Xylenes (total)	0.031		0.020	ppmv

ND = Not Detected

EPA TO-3 - BTEX

Client Name: Advanced Technology Laboratories
Client ID: 28622-006/143M-V-1
LAB ID: 133786-0006-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-5

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 29 AUG 98

Parameter	Result	Qualifier	RL	Units
Benzene	ND		0.020	ppmv
Toluene	0.021		0.020	ppmv
Ethylbenzene	ND		0.020	ppmv
Xylenes (total)	0.029		0.020	ppmv

ND = Not Detected

EPA TO-3 - BTEX

Client Name: Advanced Technology Laboratories
Client ID: 28622-007/152-V-1
LAB ID: 133786-0007-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-5

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 29 AUG 98

Parameter	Result	Qualifier	RL	Units
Benzene	ND		0.020	ppmv
Toluene	ND		0.020	ppmv
Ethylbenzene	ND		0.020	ppmv
Xylenes (total)	ND		0.020	ppmv

ND = Not Detected

EPA TO-3 - TVPH by GC

Client Name: Advanced Technology Laboratories
Client ID: 28622-001/BL9-V-1
LAB ID: 133786-0001-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-5

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
TVPH as Gasoline	2.2	C	1.0	ppm (v/v)

C = Sample chromatographic pattern is not indicative of the standard pattern used to calibrate the gas chromatograph.

EPA TO-3 - TVPH by GC

Client Name: Advanced Technology Laboratories
Client ID: 28622-002/BL9A-V-1
LAB ID: 133786-0002-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-5

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
TVPH as Gasoline	ND		1.0	ppm (v/v)

ND = Not Detected



*Environmental
Services*

EPA TO-3 - TVPH by GC

Client Name: Advanced Technology Laboratories
Client ID: 28622-003/BL18-V-1
LAB ID: 133786-0003-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-5

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
TVPH as Gasoline	ND		1.0	ppm (v/v)

ND = Not Detected



Environmental
Services

EPA TO-3 - TVPH by GC

Client Name: Advanced Technology Laboratories
Client ID: 28622-004/BL23-V-1
LAB ID: 133786-0004-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-5

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 29 AUG 98

Parameter	Result	Qualifier	RL	Units
TVPH as Gasoline	1.2	C	1.0	ppm (v/v)

C = Sample chromatographic pattern is not indicative of the standard pattern used to calibrate the gas chromatograph.

EPA TO-3 - TVPH by GC

Client Name: Advanced Technology Laboratories
Client ID: 28622-005/T1-V-1
LAB ID: 133786-0005-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-5

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 29 AUG 98

Parameter	Result	Qualifier	RL	Units
TVPH as Gasoline	1.8	C	1.0	ppm (v/v)

C = Sample chromatographic pattern is not indicative of the standard pattern used to calibrate the gas chromatograph.



Environmental
Services

EPA TO-3 - TVPH by GC

Client Name: Advanced Technology Laboratories
Client ID: 28622-006/143M-V-1
LAB ID: 133786-0006-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-5

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 29 AUG 98

Parameter	Result	Qualifier	RL	Units
TVPH as Gasoline	ND		1.0	ppm (v/v)

ND = Not Detected

EPA TO-3 - TVPH by GC

Client Name: Advanced Technology Laboratories
Client ID: 28622-007/152-V-1
LAB ID: 133786-0007-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-5

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 29 AUG 98

Parameter	Result	Qualifier	RL	Units
TVPH as Gasoline	ND		1.0	ppm (v/v)

ND = Not Detected



Environmental
Services

Fixed Gases
ASTM-D1946

Client Name: Advanced Technology Laboratories
Client ID: 28622-001/BL9-V-1
LAB ID: 133786-0001-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-1

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Methane	ND		0.00020	% (v/v)

ND = Not Detected

Fixed Gases
ASTM-D1946

Client Name: Advanced Technology Laboratories
Client ID: 28622-002/BL9A-V-1
LAB ID: 133786-0002-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-1

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Methane	ND		0.00020	% (v/v)

ND = Not Detected



Environmental
Services

Fixed Gases
ASTM-D1946

Client Name: Advanced Technology Laboratories
Client ID: 28622-003/BL18-V-1
LAB ID: 133786-0003-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-1

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Methane	ND		0.00020	% (v/v)

ND = Not Detected

Fixed Gases
ASTM-D1946

Client Name: Advanced Technology Laboratories
Client ID: 28622-004/BL23-V-1
LAB ID: 133786-0004-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-1

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Methane	ND		0.00020	% (v/v)

ND = Not Detected



*Environmental
Services*

Fixed Gases
ASTM-D1946

Client Name: Advanced Technology Laboratories
Client ID: 28622-005/T1-V-1
LAB ID: 133786-0005-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-1

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Methane	ND		0.00020	% (v/v)

ND = Not Detected

Fixed Gases
ASTM-D1946

Client Name: Advanced Technology Laboratories
Client ID: 28622-006/143M-V-1
LAB ID: 133786-0006-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-1

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Methane	ND		0.00020	% (v/v)

ND = Not Detected

Fixed Gases
ASTM-D1946

Client Name: Advanced Technology Laboratories
Client ID: 28622-007/152-V-1
LAB ID: 133786-0007-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-1

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Methane	ND		0.00020	% (v/v)

ND = Not Detected



Environmental
Services

TB-EPA 15/16-Sulfur Compounds (Tedlar bags)
Method EPA 15/16

Client Name: Advanced Technology Laboratories
Client ID: 28622-001/BL9-V-1
LAB ID: 133786-0001-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-4

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Hydrogen sulfide	ND		0.20	ppm (v/v)

ND = Not Detected



Environmental
Services

TB-EPA 15/16-Sulfur Compounds (Tedlar bags)
Method EPA 15/16

Client Name: Advanced Technology Laboratories
Client ID: 28622-002/BL9A-V-1
LAB ID: 133786-0002-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-4

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Hydrogen sulfide	ND		0.20	ppm (v/v)

ND = Not Detected

TB-EPA 15/16-Sulfur Compounds (Tedlar bags)
Method EPA 15/16

Client Name: Advanced Technology Laboratories
Client ID: 28622-003/BL18-V-1
LAB ID: 133786-0003-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-4

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Hydrogen sulfide	ND		0.20	ppm (v/v)

ND = Not Detected



Environmental
Services

TB-EPA 15/16-Sulfur Compounds (Tedlar bags)
Method EPA 15/16

Client Name: Advanced Technology Laboratories
Client ID: 28622-004/BL23-V-1
LAB ID: 133786-0004-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-4

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Hydrogen sulfide	ND		0.20	ppm (v/v)

ND = Not Detected



Environmental
Services

TB-EPA 15/16-Sulfur Compounds (Tedlar bags)
Method EPA 15/16

Client Name: Advanced Technology Laboratories
Client ID: 28622-005/T1-V-1
LAB ID: 133786-0005-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-4

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Hydrogen sulfide	ND		0.20	ppm (v/v)

ND = Not Detected



Environmental
Services

TB-EPA 15/16-Sulfur Compounds (Tedlar bags)
Method EPA 15/16

Client Name: Advanced Technology Laboratories
Client ID: 28622-006/143M-V-1
LAB ID: 133786-0006-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-4

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Hydrogen sulfide	ND		0.20	ppm (v/v)

ND = Not Detected



Environmental
Services

TB-EPA 15/16-Sulfur Compounds (Tedlar bags)
Method EPA 15/16

Client Name: Advanced Technology Laboratories
Client ID: 28622-007/152-V-1
LAB ID: 133786-0007-SA
Matrix: AIR
Authorized: 28 AUG 98
Instrument: GC-4

Sampled: 27 AUG 98
Prepared: N/A
Dilution: 1.0

Received: 28 AUG 98
Analyzed: 28 AUG 98

Parameter	Result	Qualifier	RL	Units
Hydrogen sulfide	ND		0.20	ppm (v/v)

ND = Not Detected

QC LOT ASSIGNMENT REPORT - MS QC
Air Toxics

Laboratory Sample Number	QC Matrix	QC Category	QC Lot Number (DCS)	QC Run Number (SCS/BLANK/LCS)	MS QC Run Number (SA, MS, SD, DU)
133786-0001-SA	AIR	EPA-15-16	28 AUG 98-A4	28 AUG 98-A4	
133786-0002-SA	AIR	EPA-15-16	28 AUG 98-A4	28 AUG 98-A4	
133786-0003-SA	AIR	EPA-15-16	28 AUG 98-A4	28 AUG 98-A4	
133786-0004-SA	AIR	EPA-15-16	28 AUG 98-A4	28 AUG 98-A4	
133786-0005-SA	AIR	EPA-15-16	28 AUG 98-A4	28 AUG 98-A4	
133786-0006-SA	AIR	EPA-15-16	28 AUG 98-A4	28 AUG 98-A4	
133786-0007-SA	AIR	EPA-15-16	28 AUG 98-A4	28 AUG 98-A4	
133786-0001-SA	AIR	TO-3-GAS-G	28 AUG 98-A5	28 AUG 98-A5	
133786-0002-SA	AIR	TO-3-GAS-G	28 AUG 98-A5	28 AUG 98-A5	
133786-0003-SA	AIR	TO-3-GAS-G	28 AUG 98-A5	28 AUG 98-A5	
133786-0004-SA	AIR	TO-3-GAS-G	28 AUG 98-A5	28 AUG 98-A5	
133786-0005-SA	AIR	TO-3-GAS-G	28 AUG 98-A5	28 AUG 98-A5	
133786-0006-SA	AIR	TO-3-GAS-G	28 AUG 98-A5	28 AUG 98-A5	
133786-0007-SA	AIR	TO-3-GAS-G	28 AUG 98-A5	28 AUG 98-A5	
133786-0001-SA	AIR	TO-3-BTEX	28 AUG 98-A5	28 AUG 98-A5	
133786-0002-SA	AIR	TO-3-BTEX	28 AUG 98-A5	28 AUG 98-A5	
133786-0003-SA	AIR	TO-3-BTEX	28 AUG 98-A5	28 AUG 98-A5	
133786-0004-SA	AIR	TO-3-BTEX	28 AUG 98-A5	28 AUG 98-A5	
133786-0005-SA	AIR	TO-3-BTEX	28 AUG 98-A5	28 AUG 98-A5	
133786-0006-SA	AIR	TO-3-BTEX	28 AUG 98-A5	28 AUG 98-A5	
133786-0007-SA	AIR	TO-3-BTEX	28 AUG 98-A5	28 AUG 98-A5	
133786-0001-SA	AIR	ASTM-D1946	28 AUG 98-A1	28 AUG 98-A1	
133786-0002-SA	AIR	ASTM-D1946	28 AUG 98-A1	28 AUG 98-A1	
133786-0003-SA	AIR	ASTM-D1946	28 AUG 98-A1	28 AUG 98-A1	
133786-0004-SA	AIR	ASTM-D1946	28 AUG 98-A1	28 AUG 98-A1	
133786-0005-SA	AIR	ASTM-D1946	28 AUG 98-A1	28 AUG 98-A1	
133786-0006-SA	AIR	ASTM-D1946	28 AUG 98-A1	28 AUG 98-A1	
133786-0007-SA	AIR	ASTM-D1946	28 AUG 98-A1	28 AUG 98-A1	

DUPLICATE CONTROL SAMPLE REPORT
Air Toxics
Project: 133786

Category: EPA-15-16 EPA Method 15-16
Matrix: AIR
QC Lot: 28 AUG 98-A4
Concentration Units: ppm (v/v)

Date Analyzed: 28 AUG 98

Analyte	Spiked	Concentration Measured		%Recovery		RPD	Acceptance Limits	
		DCS1	DCS2	DCS1	DCS2		Recov.	RPD
Hydrogen sulfide	0.950	1.20	1.24	127	130	3.0	60-160	25

Category: TO-3-GAS-G Method TO-3 - TVPH as Gasoline
Matrix: AIR
QC Lot: 28 AUG 98-A5
Concentration Units: ppm (v/v)

Date Analyzed: 28 AUG 98

Analyte	Spiked	Concentration Measured		%Recovery		RPD	Acceptance Limits	
		DCS1	DCS2	DCS1	DCS2		Recov.	RPD
TVPH as Gasoline	9.19	10.4	10.3	113	112	1.3	70-125	20

Category: TO-3-BTEX Method TO-3 - BTEX
Matrix: AIR
QC Lot: 28 AUG 98-A5
Concentration Units: ppmv

Date Analyzed: 28 AUG 98

Analyte	Spiked	Concentration Measured		%Recovery		RPD	Acceptance Limits	
		DCS1	DCS2	DCS1	DCS2		Recov.	RPD
Benzene	1.01	0.936	0.895	93	89	4.4	70-125	20
Toluene	1.02	1.00	0.921	98	90	8.2	70-125	20

Category: ASTM-D1946 Fixed Gases (ASTM-D1946)
Matrix: AIR
QC Lot: 28 AUG 98-A1
Concentration Units: % (v/v)

Date Analyzed: 28 AUG 98

Analyte	Spiked	Concentration Measured		%Recovery		RPD	Acceptance Limits	
		DCS1	DCS2	DCS1	DCS2		Recov.	RPD
Methane	0.0100	0.0105	0.0105	105	105	0.0	80-120	20

Calculations are performed before rounding to avoid round-off errors in calculated results.

METHOD BLANK REPORT

Air Toxics

Project: 133786

Test: EPA-15-16-TB-G

Method EPA 15/16 - Sulfur Compounds

Matrix: AIR

QC Run: 28 AUG 98-A4

Date Analyzed: 28 AUG 98

Analyte	Result	Units	Reporting Limit
Hydrogen sulfide	ND	ppm (v/v)	0.20

Test: TO-3-TVPH-GAS-TB-G

Method TO-3 - TVPH as Gasoline

Matrix: AIR

QC Run: 28 AUG 98-A5

Date Analyzed: 28 AUG 98

Analyte	Result	Units	Reporting Limit
TVPH as Gasoline	ND	ppm (v/v)	1.0

Test: TO-3-BTEX-TB-G

Method TO-3 - BTEX

Matrix: AIR

QC Run: 28 AUG 98-A5

Date Analyzed: 28 AUG 98

Analyte	Result	Units	Reporting Limit
Benzene	ND	ppmv	0.020
Toluene	ND	ppmv	0.020
Ethylbenzene	ND	ppmv	0.020
Xylenes (total)	ND	ppmv	0.020

Test: ASTM-D1946-TB

Method ASTM-D1946 - Fixed Gases

Matrix: AIR

QC Run: 28 AUG 98-A1

Date Analyzed: 28 AUG 98

Analyte	Result	Units	Reporting Limit
Methane	ND	% (v/v)	0.00020

ND = Not Detected

CHANN CLUOL RECORD

0.55.86

FOR LABORATORY USE ONLY:

Advanced Technology Laboratories 1510 E. 33rd Street Signal Hill, CA 90807 (562) 989-4045 • FAX (562) 989-4040		Batch #: _____ D.O. # _____ P.O. #: _____ Logged By: _____ Date: _____ Time: _____		Method of Transport Walk-in <input type="checkbox"/> Courier <input type="checkbox"/> UPS <input type="checkbox"/> FED. EXP. <input type="checkbox"/> ATL <input checked="" type="checkbox"/>		Sample Condition Upon Receipt 1. CHILLED Y <input type="checkbox"/> N <input type="checkbox"/> 4. SEALED Y <input type="checkbox"/> N <input type="checkbox"/> 2. HEADSPACE (VOA) Y <input type="checkbox"/> N <input type="checkbox"/> 5. # OF SPLS MATCH COC Y <input type="checkbox"/> N <input type="checkbox"/> 3. CONTAINER INTACT Y <input type="checkbox"/> N <input type="checkbox"/> 6. PRESERVED Y <input type="checkbox"/> N <input type="checkbox"/>	
--	--	--	--	--	--	--	--

Client: ATL Attn: Rachelle Arada	Address: _____ City: _____ State: _____ Zip: _____	Project #: _____ Sampler: Same as above	TEL: () _____ FAX: () _____
Relinquished by: Quinn Sullivan Date: 8-28-98 Time: 0900 Relinquished by: Quinn Sullivan Date: 8-28-98 Time: 5:30 Relinquished by: _____ Date: _____ Time: _____			

SHIP TO LAB (SUB CONTRACTOR)

TEST: _____

ATL #: _____ DATE: _____

CLIENT I.D.: _____

Pin Name: _____ Date: _____

Signature: _____

Send Report To: _____

Attn: _____

Co: _____

Address: _____

City: _____ State: _____ Zip: _____

I hereby authorize ATL to perform the work indicated below:
 Project Mgr /Submitter: _____

Sample Archive/Disposal:
☐ Laboratory Standard
☐ Other
☐ Return To: _____

* \$10.00 FEE PER HAZARDOUS SAMPLE DISPOSAL.

LAB USE ONLY: Batch #: Lab No.	Sample Description	Sample I.D.	Date	Time	SINGLE APPROPRIATE MATRIX										PRESERVATION	QA/QC	REMARKS
					OTHER	WIPES • FILTER	AIR	DRINKING WATER	WATER • WASTEWATER	OIL • SOLVENT • LIQUID	SOLID • SOIL • SLUDGE	OTHER	TAT	#	Type		
1	281022-001/BL9-V-1	8/27															
2	002/BL9A-V-1																
3	003/BL9-V-1																
4	004/BL23-V-1																
5	005/11-V-1																
6	006/143M-V-1																
7	007/152-V-1																

Special Instructions/Comments:
PO #: (To follow)
please fax results!
Note holding time!

Preservatives:
 H=HCl N=HNO₃ S=H₂SO₄ C=4°C
 Z=Zn(AC)₂ O=NaOH T=Na₂SO₃

Container Types: T=Tube V=VOA L=Liter P=Pin J=Jar B=Tedlar G=Glass P=Plastic M=Metal

Emergency: B=Next workday
 TAT: A=Overnight ≤ 24 hr
 Critical: C=2 Workdays
 Urgent: D=3 Workdays
 Routine: E=7 Workdays

DISTRIBUTION: White with report. Yellow to folder. Pink to submitter

rg of

DISTRIBUTION: White with report Yellow to folder Pink to submitter